

SURVEY & REMONUMENTATION
APR 07 1995
COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
Dickinson
 (County)

Located In:

Corner Code #/

- | | | |
|------------------------------------|---------------------------|------------|
| 1. Public Land Survey Section 20 | T <u>39N</u> R <u>28W</u> | <u>E-9</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

REGISTER OF DEEDS
 DICKINSON COUNTY
 1994 DEC -9 PM 3:44
RECORDED
 Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____
- Section corner to 20, 21, 28 & 29

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, John R. Garske, in a field survey on October 25 and 26, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1849 - Township subdivision by James H. Mullett, D.S. Original bearing trees: hemlock 12" - S61°W, 29 links; hemlock 14" - N69°E, 26 links.

1934 - Dickinson Co. Rd. Commission E.R. Nelson set iron pipe from "computations of coordinates".

1937 - Dickinson Co. Rd. Commission R.O.W. map shows section corner with distances east, west and north to road.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 2" pipe protruding 32" above ground. I believe this pipe to be E.R. Nelson's from above. Chainage to east checks well with Dickinson Co. Rd. Commission dimension. Accepted pipe as corner set by Nelson in 1934.

ACCEPTED BY THE DICKINSON COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON
1-23-95
ROP
 COUNTY REPRESENTATIVE

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Replaced existing pipe with aluminum Dickinson County monument and drove pipe in 0.4 feet north of new monument. Established the following references: 7" balsam - N43°E, 8.32 feet; 9" spruce - S05°E, 33.62 feet; 6" maple - S83°W, 31.28 feet; 6" maple - N20°W, 62.73 feet; set carsonite witness post - S.W., 1.46 feet.



Signed by John R. Garske
 Surveyor's Michigan License No. 28410

Date 12/8/94