

RECORDED

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

1999 NOV 29 AM 10:31

For corners in

Dickinson Located In: Corner Code #
 (County)
Waucedah Twp.
 1. Public Land Survey T 39N R 28W E-10
 T R G-10
 T R
 T R
 2. Property Controlling S T R
 in Section S T R
 3. Miscellaneous S T R
 Property in Sec. S T R

MAR 24 2000

REGISTER OF DEEDS
DICKINSON COUNTY
PO BOX 100
DICKINSON, MI 49821

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____ SECTION _____
5. Private Claims _____

I, Robert F. Perkins, in a field survey on Oct. 12, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

E-10 ¼ Corner 29/28
 Post by J.H. Mullett, D.S. 1849
 Original Bearing Trees
 Maple 3" N48°W 05 Lks.
 Maple 3" S35°E 08 Lks.

G-10 ¼ Corner 28/27
 Post by J.H. Mullett, D.S. 1849
 N. Side Windfall
 Original Bearing Trees
 Birch 6" S11°E 10 Lks.
 Elm 16" S87°E 15 Lks.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

E-10 No Evidence of Original Corner or Accessories Found.
 Found K.C. Corp. 1" Pipe Marker with 4" Brass Cap as Established by Neal Sperhake, RLS in 1963.
 W.Pine N55°W 33½ L.(Found)
 Corner Report #760

G-10 No Evidence of Original Corner or accessories found.
 Corner Location established by Single Proportionate Method between Section Corner ½ Mile North and ½ Mile South.

ACCEPTED BY THE DICKINSON COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON 11-23-99

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E-10 Accepted Marker described in B above.
 New Witnesses
 W.Pine 12" S77°E(M.B.) 4.19' Nail/Tag
 W.Pine 16" N52°W(M.B.) 22.07' Nail/Tag
 R.Pine 12" N5°E(M.B.) 47.38' Nail/Tag
 R.Pine 18" S14°W(M.B.) 42.96' Nail/Tag
 Placed Carsonite Marker 1.0' South

G-10 Set 2½" Stamped D.C.Remon. Marker as described in "B" above.
 New Witnesses
 Maple 7" N27°W(M.B.) 26.24' Nail/Tag
 Maple 12" N55°E(M.B.) 46.85' Nail/Tag
 Maple 7" N69°W(M.B.) 31.76' Nail/Tag
 Ash 4" S03°W(M.B.) 21.53' Nail/Tag

RA R A
COUNTY REPRESENTATIVE

Signed by Robert F. Perkins
Surveyor's Michigan License No. 12027

Date Nov, 5, 1999

Libee 2

Page 468