

**SURVEY &  
REMONUMENTATION  
APR 07 1995  
COMMISSION**

**LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in  
Dickinson  
(County)

Located In: \_\_\_\_\_ Corner Code #/ # \_\_\_\_\_

- |                                    |    |   |     |   |     |     |
|------------------------------------|----|---|-----|---|-----|-----|
| 1. Public Land Survey Section      | 15 | T | 39N | R | 28N | G-6 |
|                                    |    | T |     | R |     |     |
|                                    |    | T |     | R |     |     |
|                                    |    | T |     | R |     |     |
| 2. Property Controlling in Section | S  |   | T   |   | R   |     |
|                                    | S  |   | T   |   | R   |     |
| 3. Miscellaneous Property in Sec.  | S  |   | T   |   | R   |     |
|                                    | S  |   | T   |   | R   |     |

REGISTER OF DEEDS  
 DICKINSON COUNTY  
 AND NEIGHBORING COUNTIES  
 1994 DEC -9 PM 3:44  
 RECORDED

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
5. Private Claims \_\_\_\_\_
- 1/4 corner Sections 15 & 16

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, \_\_\_\_\_, in a field survey on October 24, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

1849 - Township subdivision by James H. Mullett. Elm 15" - N24°E, 12 links; elm 12" - N66°W, 30 links.

1915 - Dickinson County Road commission - field notes indicate an old squared partially burnt cedar stake at corner, 263 feet north of railroad. They also found a fallen 18" blazed elm - N70°W, 18.4 feet from stike (probably original B.T.). Set a new squared, scribed 3" cedar stake. Elm 24" - S45°W, 36.9 feet; maple 15" - N42°E, 63.0 feet.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1 1/4" diameter iron pin at corner of ancient fences running south and west. An old rotted square post was lying next to pin. An old Celotex Corporation location poster is on corner fence post. Chained south along old fence 265 feet ± to aproximate centerline of old R.R. grade which checks well with 1915 Dickinson Co. Rd. Commission dimension from above. Accepted pin as corner position.

ACCEPTED BY THE DICKINSON COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON  
1-23-95  
ROIP  
COUNTY REPRESENTATIVE

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Replaced iron pin with aluminum Dickinson County monument. Drove 1 1/4" pin back in alongside new monument. Established the following references: 8" spruce - N15°E, 28.95 feet; 5" balsam - S48°E, 87.31 feet; 7" spruce - S24°W, 69.69 feet; 4" balsam - N60°W, 8.88 feet; set carsonite witness post - N.S. - 0.97 feet.

Signed by John R. Garske  
Surveyor's Michigan License No. 28410

Date 12/8/94

