

SURVEY & REMONUMENTATION

APR 07 1995

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Dickinson

(County)

Located in:

Corner Code #H

1. Public Land Survey Section 22 T 39N R 28W H-9
 T _____ R _____
 T _____ R _____
 T _____ R _____
2. Property Controlling in Section S _____ T _____ R _____
 S _____ T _____ R _____
3. Miscellaneous Property in Sec. S _____ T _____ R _____
 S _____ T _____ R _____
4. Lot No. _____, Recorded Plat _____
5. Private Claims _____
 1/4 corner 22 & 27

REGISTER OF DEEDS
MICHIGAN COUNTY
PROPERTY RECORDS DIVISION

1994 DEC -9 PM 3:45

RECORDED

Register of Deeds Stamp & File Number

I, John R. Garske, in a field survey on October 10, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

Original survey by James H. Mullet, D.S., in August 1849. Set post. Original bearing trees: beech 6" - N33°W, 44 links; hemlock 18" - S81°E, 12 links.

1935± - W.C. Johnson traversed to corner. Doesn't say what he found.


B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found old fence line running in four directions at corner location which measures 2644 feet from the corner to the east. Occupation lines check very good from this fence intersection. Accepted fence intersection as corner position, due to its longevity (over 50 years) and its harmonious position with all residents.

ACCEPTED BY THE DICKINSON COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON 1-23-95
RJP
 COUNTY REPRESENTATIVE

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set Dickinson County monument at fence intersection. Established following references: carsonite rail - S.W., 1.84 feet; 4" spruce - N81°W, 10.09 feet; 9" spruce - N54°E, 4.87 feet; 4" spruce - S06°E, 31.75 feet; 8" spruce - S25°W, 26.89 feet.



Signed by John R. Garske
 Surveyor's Michigan License No. 28410

Date 12/8/94

Sub 2

H-9

Page 127