

SURVEY & REMONUMENTATION

APR 07 1995

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in Dickinson
 (County)

Located In: _____ Corner Code #/ # _____

- | | | |
|--|-----------------|-------|
| 1. Public Land Survey Section 11 T <u>39N</u> R <u>28W</u> | _____ | J-5 |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling S _____ T _____ R _____ | _____ | _____ |
| in Section S _____ T _____ R _____ | _____ | _____ |
| 3. Miscellaneous S _____ T _____ R _____ | _____ | _____ |
| Property in Sec. S _____ T _____ R _____ | _____ | _____ |

REGISTER OF DEEDS
 DICKINSON COUNTY
 MONUMENTAL RECORDS

1994 DEC -9 PM 3:45

RECORDED

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

1/4 corner to Sections 11 & 14

I, John R. Garske, in a field survey on October 10, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

Original survey by James H. Mullet, D.S., in August 1849, set post. Original bearing trees: tamarack 8" - N40°E, 19 links; tamarack 8" - N45°W, 16 links.

1912 - M. Bacco, Dickinson Co. Rd. Commission, found sq. cedar post and remains of original tamarack B.T. He didn't mention if he set new monument or bearing trees.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I found a 1 1/2" O.D. iron pipe at corner location at the end of an east-west fence running west. Two B.T.s are facing the pipe with a line cut west from the pipe. The iron pipe has obviously been used and accepted for a number of years with a traverse line running east to the highway. I am accepting it based on use and acceptance.

ACCEPTED BY THE DICKINSON COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON 1-23-95
RGP
 COUNTY REPRESENTATIVE

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Replaced iron pipe with Dickinson County aluminum monument. Established following references: carsonite rail - North, 1.00 feet; 10" cedar - N55°E, 15.91 feet; 3" cedar - S51°E, 20.08 feet; 6" cedar (existing) - S34°W, 14.76 feet; 6" cedar (existing) - N50°W, 8.17 feet.



Signed by John R Garske

Date 12/8/94

Surveyor's Michigan License No. 28410

Liber 2

J-5

Page 133