

SURVEY & REMONUMENTATION

APR 07 1995

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in Dickinson
(County)

Located In: _____ Corner Code L-11

- 1. Public Land Survey Section 36T 39NR 28W L-11
 T _____ R _____
 T _____ R _____
 T _____ R _____
- 2. Property Controlling in Section S _____ T _____ R _____
 S _____ T _____ R _____
- 3. Miscellaneous Property in Sec. S _____ T _____ R _____
 S _____ T _____ R _____

REGISTER OF DEEDS
MICHIGAN COUNTY
CORNER RECORDATION UNIT 15501

1994 DEC -9 PM 3:45

RECORDED

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

1/4 corner Sections 25 & 36

I, John R. Garske, in a field survey on October 24, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Original survey by James H. Mullet, D.S., in August 1849. Set post. Original bearing trees: Beech 16" - S353°E, 41 links; Beech 6" - N2°E, 06 links.

1941 - Dickinson Co. Rd. Commission survey of "Stunt Beck Road" shows distance of 1279.2 feet from P.I. west to 1/4 corner.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found an old 2" iron pipe using distance from Dickinson County Road Commission chaining west along an ancient fence from the centerline of road. Survey corner is at fence intersection with wooden post marking corner. An 18" hemlock with a chest blaze faces the pipe. Accepted iron pipe as corner position.

ACCEPTED BY THE DICKINSON COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON 1-23-95
ROP
COUNTY REPRESENTATIVE

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Drove Dickinson County aluminum monument inside existing pipe. Established following references: 7" sugar maple - N43°E, 17.88 feet; 18" existing hemlock - S50°E, 25.83 feet; 7" sugar maple - s30°E, 40.34 feet; 6" sugar maple - s07°E, 30.26 feet; carsonite rail - S.W. 0 54 feet; 8" sugar maple - N54°W, 37.14 feet.

Signed by John R Garske
Surveyor's Michigan License No. 28410

Date 12/8/94



Liberty 2 L-11

Page 136