

DEC 18 1995

COMMISSION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED

1995 NOV 21 AM 11:25

For corners in

Dickinson  
(County)

Located In:

Corner Code #

- 1. Public Land Survey      T 39N R 29W      A-2
- T        R             B-1
- T        R             \_\_\_\_\_
- T        R             \_\_\_\_\_
- 2. Property Controlling    S        T        R        \_\_\_\_\_
- in Section                S        T        R        \_\_\_\_\_
- 3. Miscellaneous            S        T        R        \_\_\_\_\_
- Property in Section    S        T        R        \_\_\_\_\_

REGISTER OF DEEDS  
CLERK  
NOV 21 1995

Register of Deeds Stamp & File Number

- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

I, Robert F. Perkins, in a field survey on Oct. 10, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
6	5	4	3	2	1							
7	8	9	10	11	12							
18	17	16	15	14	13							
19	20	21	22	23	24							
30	29	28	27	26	25							
31	32	33	34	35	36							

A. Description of original monument and accessories and/or subsequent restoration:

- A-2 West 1/4 Corner, Section 6  
Post by J. Mullett, D.S. 1847  
Original Bearing Trees  
S.Pine 6" N33°W 5 Lks.  
S.Pine 4" S 9°W 9 Lks.
- B-1 North 1/4 Corner, Section 6  
Post by J. Mullett, D.S. 1847  
Original Bearing Trees  
Maple 4" N59°E 30 Lks.  
Birch 10" N 8°W 21 Lks.

ACCEPTED BY THE DICKINSON COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON

11-20-95

R.F.P.

COUNTY REPRESENTATIVE

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- A-2 No Evidence of Original Corner or Accessories Found.  
Found City of Norway Concrete Monument buried 8" in Road L.  
Appears on Sheet 1-F, City of Norway Land Record.  
Corner Researched in 1994.
- B-1 No Evidence of Original Corner or Accessories Found.  
Found 2 1/2" Iron Pipe in E-W Fence and 1 Bearing Tree- Oak 8" N70°W 45' (Dead).  
Per Sheet 3-D, City of Norway Land Corner Record.  
Corner Researched in 1994.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- A-2 Placed Monument Box over Existing Monument.  
S.E. Corner House (Fornetti), N41°W (M.B.) 130.30'.  
N.W. Corner House (Hart), S66°E (M.B.) 168.60'  
Concrete Monument N85°W (M.B.) 33.00'  
Concrete Monument S85°E (M.B.) 33.00'  
Carsonite Marker S85°E (M.B.) 32.3'
- B-1 Replaced Existing Pipe with 2 1/2" Stamped Remon. Monument.  
R.Maple 18" S71°E (M.B.) 22.55'  
Ironwood 5" S17°E (M.B.) 50.00'  
R.Maple 8" S51°W (M.B.) 12.10'  
Oak 14" N89°W (M.B.) 34.70'  
Carsonite Marker South 1.0'  
Bearing Trees have Duplex Nail at Base.

Signed by Robert F. Perkins

Date Nov. 7, 1995

Surveyor's Michigan License No. 12027

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 24, 1981

