

**SURVEY & REMONUMENTATION**

DEC 18 1995

**COMMISSION**

**LAND CORNER RECORDATION CERTIFICATE**

Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED

FEB -9 AM 9:17

For corners in Dickinson  
(County)

Located In:

Corner Code #

REGISTERED DEEDS  
MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS  
REGISTERED LAND SURVEYORS

- |                                      |                           |               |
|--------------------------------------|---------------------------|---------------|
| 1. Public Land Survey                | T <u>39N</u> R <u>29W</u> | <u>C-2</u>    |
|                                      | T _____ R _____           | _____         |
|                                      | T _____ R _____           | _____         |
|                                      | T _____ R _____           | <u>Sec. 1</u> |
| 2. Property Controlling in Section   | S _____ T _____ R _____   | _____         |
|                                      | S _____ T _____ R _____   | _____         |
| 3. Miscellaneous Property in Section | S _____ T _____ R _____   | _____         |
|                                      | S _____ T _____ R _____   | _____         |

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
5. Private Claims \_\_\_\_\_  
 1/4 Corner common to Sections 5/6

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	•	5	4	3	2	1						
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, **Robert F. Perkins**, in a field survey on Feb. 3, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

- 1849 Township Subdivision by J. Mullett, D.S.  
 Y. Pine 18" N30°E 15 L.  
 R. Pine 6" N61°W 18 L.  
 City of Norway Records (Sheet 5-F) indicates Concrete Monument in Road.
- 1970 R. Perkins found Concrete Monument buried 36" in Road.  
 Placed 1" x 36" Iron Pipe over Monument.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

Found 1" Iron Pipe in Asphalt Road (noted above)

ACCEPTED BY THE DICKINSON COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON

2-7-95

ROF

COUNTY REPRESENTATIVE

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

- Existing 1" Iron Pipe in centerline N-S Road and ± 13 feet North of centerline Road East.  
 Set Dickinson County Remonumentation Witness Corner 30.0 feet West of Pipe.  
 P.Pole S30°E (M.B.) 53.69' (Nail & I.D. Cap)  
 P.Pole N27°E (M.B.) 123.40' (Nail & I.D. Cap)  
 2" Steel Post (Road Sign) N58°E (M.B.) 35.00'

Signed by Robert F. Perkins  
 Surveyor's Michigan License No. 12027

Date Feb. 3, 1995

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN 28, 1971  
 REVISED MAY 14, 1978  
 REVISED JAN., 1983



*Suber 2 Page 145*