

RECORDED

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

1998 JUN 12 AM 8:59

For corners in

<u>Dickinson</u>	Located In:	Corner Code #
(County) City of Norway		
1. Public Land Survey	T39N R29W	C-4
	T R	C-5
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

REGISTER OF DEEDS  
DICKINSON COUNTY  
IRON MOUNTAIN MI 49901

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

SECTION

I, Robert F. Perkins, in a field survey on Feb. 16, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

ACCEPTED BY THE DICKINSON COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON

6-4-98  
RFP

COUNTY REPRESENTATIVE

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7	●	8		9		10		11		12	
5		●										
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

A. Description of original monument and accessories and/or subsequent restoration.

C-4 East 1/4 Corner, Section 7 Wood Post by James H. Mullett, D.S. 1849. Original Bearing Trees Spruce 4" S35°W 0.07 L. Tamarack 6" S51°E 0.14 L.	C-5 S.E. Corner, Section 7 Wood Post by James H. Mullett, D.S. 1849 Original Bearing trees Y.Pine 10" S12°W 0.08 L. Aspen 10" N55°E 0.10 L.
---	---

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner.

C-4 No evidence of Original Corner or Accessories Found. Found 1" Iron Pipe as referred to on Sheet 5-J of City of Norway Land Corner Records. Corner previously Recorded by E. Kazianka, P.S. in 1980 L.C.R.C. #272.	C-5 No evidence of Original Corner or Accessories Found. Found 1" Iron Pipe at Fence Corner. Location agrees with City of Norway Land Corner Records (1938) Sheet 5-L. Corner previously Recorded by E. Kaziaka, PS in 1980, L.C.R.C. #271.
--	--

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner.

C-4 Replaced 1" Iron Pipe described in B above with 2 1/2" Stamped D.C. Remon. Marker. New Witnesses: Tamarack 10" S51°E (M.B.) 26.45' Nail/Tag Tamarack 16" S60°W (M.B.) 45.82' Nail/Tag Tamarack 10" N69°W (M.B.) 35.87' Nail/Tag Tamarack 8" N67°E (M.B.) 41.00' Nail/Tag Carsonite Marker 1.0' North.	C-5 Replaced 1" Iron Pipe described in B above with 2 1/2" Stamped D.C. Remon. Marker. New Witnesses: Oak 6" N12°E (M.B.) 16.22' Nail/Tag Oak 12" N51°E (M.B.) 24.32' Nail/Tag Oak 6" S54°W (M.B.) 22.30' Nail/Tag R.Maple 4" S28°E (M.B.) 19.25' Nail/Tag 4' Boulder S22°W (M.B.) 16' Carsonite Marker South 0.70'
---	--

Signed by Robert F. Perkins  
Surveyor's Michigan License No. 12027

Date June 11 1998

