

RECORDED

1999 NOV 29 AM 10:31

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Dickinson</u>	Located In:	Corner Code #
(County) Norway Twp.		
1. Public Land Survey	T 39NR29W	<u>I-10</u>
	T ___ R ___	K-10
	T ___ R ___	
	T ___ R ___	
2. Property Controlling in Section	S ___ T ___ R ___	
	S ___ T ___ R ___	
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	
	S ___ T ___ R ___	

REGISTERED DEEDS
DICKINSON COUNTY
NOV 29 1999

Register of Deeds Stamp & File Number

MAR 24 2000

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____ SECTION _____

I, Robert F. Perkins, in a field survey on Sept. 28, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

K-10 1/4 Corner 26/25
(L. 2, Pg. 203)
Post by J.H. Mullett, D.S. 1849
Original Bearing Trees
W.Pine 22" N45°E 26 Lks.
W.Pine 24" S68°W 9 Lks.

I-10 1/4 Corner 27/26
Post by J.H. Mullett, D.S. 1849
Original Bearing Trees
W.Pine 48" N40°E 6 Lks.
W.Oak 12" N67°W 34 Lks.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

K-10 11-20-95 James H. Moore, P.S.
monumented Corner as described
on L.C.R.C. Liber 2, P. 203.

I-10 No Evidence of Original Corner
or accessories Found.
Found 1" Sq. Iron Bar Penn Iron
Co. Corner projecting 0.4' by
running South from Section Corner.
Corner is ± 35' East of River Bank.

ACCEPTED BY THE DICKINSON COUNTY
SURVEY PLER GROUP AS THE OFFICIAL
CORNER UNDER MICHIGAN PUBLIC ACT
345 OF 1990 AT A MEETING HELD ON
11-23-99

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-10 7-28-99 Corner destroyed by Road
Reconstruction. Corner Re-established
from 1995 Witnesses.
Placed 3 1/2" Stamped D.C. Remon. Corner
in Monument Box.
S.E. Corner Garage N23°E 145.63'
R. Pine 5" N78°E 105.92'
P.Pole S17°W 33.50'
Stamped W.C. N38°W 37.40' with
Carsonite Marker.

I-10 Accepted iron bar described in "B"
above as Best Remaining Evidence
of Corner Location. Placed 2 1/2"
Stamped D.C. Remon. Corner adjacent
to existing iron bar.

New Witnesses:
W. BIRCH 12" S52°W(M.B.) 58.97' NAIL/TAG
ASH 8" S81°W(M.B.) 51.21' NAIL/TAG
P.POLE North 148.7' NAIL/TAG
P.POLE S3 1/2°E(M.B.) 118.59' NAIL/TAG
C/L Power Line 5' East
Placed CARSONITE MARKER 1' East
NOV. 5, 1999

Signed by Robert F. Perkins
Surveyor's Michigan License No. 12027

Date

