

DEC 18 1995

COMMISSION

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED

1995 NOV 21 AM 11: 27

For corners in

Dickinson (County)

Located In:

Corner Code #

- 1. Public Land Survey T 39N R 29W K-3
2. Property Controlling in Section S T R
3. Miscellaneous Property in Section S T R
4. Lot No. , Recorded Plat
5. Private Claims

REGISTER OF DEEDS
DICKINSON COUNTY

Register of Deeds Stamp & File Number

I, Robert F. Perkins, in a field survey on Nov. 6, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

K-3 Southeast Corner, Section 2
Post J.H. Mullett, D.S. 1849
Original Bearing Trees
Beech 10" N65°E 15 Lks.
Beech 6" N60°W 15 Lks.

ACCEPTED BY THE DICKINSON COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON


11-20-95
RFP
COUNTY REPRESENTATIVE

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

K-3 No Evidence of Original Corner or Accessories Found.
Corner removed by recent County Road Reconstruction.
Corner researched in 1994 by Sundberg & Carlson.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-3 Southeast Corner, Section 2
Set 2 1/2" Stamped Dickinson County Remonumentation Monument buried 8" in Shoulder of Road.
Corner Re-established from Prior Surveys and Witnesses.
New Witnesses
Power Pole #60-23745 S70°W (M.B.) 6.74'
Power Pole #95-03574 S81°E (M.B.) 47.22'
Lynn 36" East (M.B.) 71.0'
Willow 20" S34°E (M.B.) 158.80'
Corner is 10.3' West of West E.O.M. Var.= ±8°



Signed by [Signature]

Date Nov. 7, 1995

Surveyor's Michigan License No. 12027