

RECORDED

1996 DEC 18 AM 11:16

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

DICKINSON

(County)

Located In:

Corner Code #

NORMAY TWP.

- 1. Public Land Survey T 39N R 29W M-1
2. Property Controlling in Section S T R
3. Miscellaneous Property in Section S T R

REGISTER OF DEEDS
DICKINSON COUNTY
IRON MOUNTAIN, MI 49801

Register of Deeds Stamp & File Number

- 4. Lot No. , Recorded Plat
5. Private Claims

Grid table with columns A-M and rows 2-13 containing numbers 6-36.

I, ROBERT F. PERKINS, in a field survey on 1-2, 19 96, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

M-1 NORTHEAST CORNER, SECTION 1
1848 SET POST H. BREVORT, D.S.
ORIGINAL BEARING TREES
SUGAR 12" N29°W 24 L.
HEMLOCK 14" N66°E 33 L.


ACCEPTED BY THE DICKINSON COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON 12-17-96 R.F.P. COUNTY REPRESENTATIVE

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

M-1 NO EVIDENCE OF ORIGINAL CORNER OR ACCESSORIES FOUND.
FOUND 1" IRON PIPE WITH BRASS CAP
D.N.R. MARKER SET BY B. BUCKLER ON 4-26-61 AND FILED ON CORNER REPORT #620.
1 MAPLE BEARING TREE 14" S. MAPLE N80°W 81 1/2 L. FOUND.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-1 FOUND ABOVE MARKER IN PLACE.
NEW WITNESSES:
N. PINE 10" S08°E (M.B.) 86.45'
TAMARACK 12" S53°W (M.B.) 26.46'
S. MAPLE 24" (BUCKLER B.T.) N80°W (M.B.) 54.2'
SPRUCE 18" N06°E (M.B.) 9.65'
CAPPED IRON BAR (SOUTH ON LINE 33.0'
PLACED CARSONITE WITNESS STAKE ± 2' SOUTH.



Signed by Robert F. Perkins

Date DECEMBER 2, 1996

Surveyor's Michigan License No. 12027

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971
REVISED MAY 14, 1975
REVISED JAN., 1983