

RECORDED

1999 NOV 29 AM 10:31

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Dickinson Located In: Corner Code #
 (County)
 Norway Twp.

1. Public Land Survey T 39NR29W I-10
 T R K-10
 T R
 T R
 T R

2. Property Controlling S T R
 in Section S T R SURVEY &
 3. Miscellaneous S T R REMONUMENTATION
 Property in Sec. S T R

MAR 24 2000

REGISTERED
 RECORDS
 DIVISION
 REGISTERED
 REGISTERED

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____ SECTION _____

I, Robert F. Perkins, in a field survey on Sept. 28, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

A. Description of original monument and accessories and/or subsequent restoration:

K-10 1/4 Corner 26/25
 (L. 2, Pg. 203)
 Post by J.H. Mullett, D.S. 1849
 Original Bearing Trees
 W.Pine 22" N45°E 26 Lks.
 W.Pine 24" S68°W 9 Lks.

I-10 1/4 Corner 27/26
 Post by J.H. Mullett, D.S. 1849
 Original Bearing Trees
 W.Pine 48" N40°E 6 Lks.
 W.Oak 12" N67°W 34 Lks.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

K-10 11-20-95 James H. Moore, P.S.
 monumented Corner as described
 on L.C.R.C. Liber 2, P. 203.

I-10 No Evidence of Original Corner
 or accessories Found.
 Found 1" Sq. Iron Bar Penn Iron
 Co. Corner projecting 0.4' by
 running South from Section Corner.
 Corner is ± 35' East of River Bank.

ACCEPTED BY THE DICKINSON COUNTY
 SURVEY PLEER GROUP AS THE OFFICIAL
 CORNER UNDER MICHIGAN PUBLIC ACT
 345 OF 1890 AT A MEETING HELD ON
11-23-99

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-10 7-28-99 Corner destroyed by Road
 Reconstruction. Corner Re-established
 from 1995 Witnesses.
 Placed 3 1/2" Stamped D.C. Remon. Corner
 in Monument Box.
 S.E. Corner Garage N23°E 145.63'
 R. Pine 5" N78°E 105.92'
 P.Pole S17°W 33.50'
 Stamped W.C. N38°W 37.40' with
 Carsonite Marker.

I-10 Accepted iron bar described in "B"
 above as Best Remaining Evidence
 of Corner Location. Placed 2 1/2"
 Stamped D.C. Remon. Corner adjacent
 to existing iron bar.
 New Witnesses:

W. BIRCH 12" S52°W(M.B.) 58.97' NAIL/TAG
 ASH 8" S81°W(M.B.) 51.21' NAIL/TAG
 P.POLE North 148.7' NAIL/TAG
 P.POLE S3 1/2°E(M.B.) 118.59' NAIL/TAG
 C/L Power Line 5' East
 Placed CARSONITE MARKER 1' East
 NOV. 5, 1999

Signed by Robert F. Perkins
 Surveyor's Michigan License No. 12027

Date

