

MAR 03 1998

RECORDED

SECTION

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

1997 DEC 10 PM 3:56

For corners in

Dickinson (County)

Located In:

Corner Code #

Breitung Twp.

Table with 3 columns: Survey Type, Located In (T, S, R), and Corner Code #. Includes entries for Public Land Survey, Property Controlling in Section, and Miscellaneous Property in Section.

REGISTER OF DEEDS DICKINSON COUNTY RON MULLETT, CLERK

Register of Deeds Stamp & File Number

- 4. Lot No.
5. Private Claims

I, Robert F. Perkins, in a field survey on Oct. 1, 1997, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules...

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

B-3 South 1/4 Corner, Section 6 Post by James Mullett 1848 Original Bearing Trees W.Pine 12" S60°E 20 Lks. Y.Pine 14" N22°E 23 Lks.

C-2 East 1/4 Corner, Section 6 Post by James Mullett, D.S. 1849 Original Bearing Trees W.Pine 6" N42°W 15 Lks. W.Pine 5" N76°E 8 Lks.

ACCEPTED BY THE DICKINSON COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON 12-9-97

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

B-3 No Evidence of Original Corner or Accessories Found. Excavated below Breen Avenue and Found 1 1/2" Iron Pipe +/- 1' below Road surface. Corner is common to Plats of Ferndale, Second Addition to East Kingsford, Lincoln Subdivision & Lincoln Subdivision No. 1. Corner Researched in 1996 Program.

C-2 No Evidence of Original Corner or Accessories Found. Found 1 1/2" Stamped Iron Pipe projecting out of Ground at Old Fence Corner. Stamped Pipe was Set by Oliver Iron Mining Co. probably prior to 1900 and is same as others found in this Area. Pipe nearly rusted off at Gound Line. Corner Researched in 1996 Program.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

B-3 Accepted above described Pipe. Replaced Pipe with 2 1/2" Stamped D.C. Remon. Corner in Monument Box. New Witnesses: Corner Conc. Foundation N76°W (M.B.) 71.20' Corner Conc. Foundation S43°E (M.B.) 89.45' N.E. Flange Nut F.H. S57°W (M.B.) 41.10' P.Pole #70-729 N55°E (M.B.) 38.45'

C-2 Accepted above described Pipe. Placed 2 1/2" Stamped D.C. Remon. Corner inside Pipe with New Aluminum Rod driven through Pipe. New Witnesses: Maple 4" S84°W (M.B.) 16.00' (Ex. B.T.) Oak 14" S15°E (M.B.) 6.89' (Ex. B.T.) Maple 10" N14°W (M.B.) 18.79' (Ex. B.T.) Maple 10" N33°E (M.B.) Carsonite Stake West

Signed by Robert F. Perkins

Date Nov. 21, 1997

Surveyor's Michigan License No. 12027

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN 28, 1978 REVISED MAY 14, 1978

