

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED

1998 DEC 14 PM 12:23

For corners in

Dickinson Located In: _____ Corner Code # _____
 (County)
City of Kingsford
 1. Public Land Survey T 39NR 31W L-3
 T _____ R _____
 T _____ R _____
 T _____ R _____
 2. Property Controlling S _____ T _____ R _____
 in Section S _____ T _____ R _____
 3. Miscellaneous S _____ T _____ R _____
 Property in Sec. S _____ T _____ R _____

REGISTER OF DEEDS
 DICKINSON COUNTY
 RON MOORE, CLERK

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, Robert F. Perkins, in a field survey on Aug. 20, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:


L-3 $\frac{1}{4}$ Corner Common to Sections 12
 Post by James H. Mullett, D.S. 1850
 Original Bearing Trees
 Tamarack 4" S20°E 17 Lk.
 Y. Birch 12" N07°W 16 Lk.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

L-3 No Evidence of Original Corner or its Accessories Found.
 Found 5/8" Capped Iron Bar (G. Carlson) as referred to in Certificate #384 buried 4" below Road Asphalt.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

L-3 Replaced above described Corner with 2 1/2" Stamped D.C. Remon. Corner in Monument Box.
 Witnesses
 Maple 14" N15°E 46.30' MDOT 1985
 Maple 16" N30°W 49.67' MDOT 1985
 P.Pole N73-17 N55°W 43.90' MDOT 1985
 P.Pole N73-28 N70°E 84.06' MDOT 1985
 N.E. Corner Garage S50°W 77.45'
 Corner is ± 1.5' South of Centerline Breen Ave.
 at Centerline Hooper St.



Signed by Robert F. Perkins

Date Oct. 24, 1998

Surveyor's Michigan License No. 12027
 ACCEPTED BY THE DICKINSON COUNTY
 SURVEY PEER GROUP AS THE OFFICIAL
 CORNER UNDER MICHIGAN PUBLIC ACT
 845 OF 1990 AT A MEETING HELD ON
12-7-98
R.F. Perkins
 COUNTY REPRESENTATIVE

002 PAGE 390