

**SURVEY &
REMONUMENTATION**

MAY 05 1997

COMMISSION

For corners in

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED

1996 DEC 18 AM 11:15

Dickinson Located In: _____ Corner Code # _____
(County)

1. Public Land Survey T 40N R 29W M-8*
T 40N R 28W A-8
T _____ R _____
T _____ R _____

2. Property Controlling S _____ T _____ R _____
in Section S _____ T _____ R _____

3. Miscellaneous S _____ T _____ R _____
Property in Sec. S _____ T _____ R _____

REGISTER OF DEEDS
DICKINSON COUNTY
IRON MOUNTAIN, MI 49801

12

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Michael Mileski, in a field survey on 7 November, 19 96 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

M-8; East One-quarter Corner Section 24, T40N, R29W;

See back of form.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

M-8; East One-quarter Corner Section 24, T40N, R29W;

Found a 1" x 42" galvanized iron pipe with a 4" brass cap as set by Mr. Buckler in 1955 and in agreement with his new bearing trees as described in Part A. Replaced Mr. Buckler's monument with a standard county monument described in Part C. Accepted as a careful and faithful reestablishment of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-8; East One-quarter Corner Section 24, T40N, R29W;

Set a 5/8" x 36" aluminum rod with a 3" aluminum cap stamped as to location projecting 4" above the ground.

Set 7" spike	E/side	4" Cedar	N08°E	9.04'
Set 7" spike	S/side	8" Tamarack	S66°E	15.88'
Set 7" spike	W/side	8" Tamarack	S19°W	26.73'
Set 7" spike	N/side	5" Cedar	N80°W	4.02'
		Location Post	North	3.0'

All of the above new bearing trees are marked with upper and lower blazes.

The lower blaze is scribed "NBT". Both blazes as well as a band around the tree at the upper blaze are painted red.

*This corner is also A-8 of T40N, R28W.

Signed by Michael Mileski
Surveyor's Michigan License No. 39091

Date 2 Dec 1996

Bk. 17M pp 10A & 11

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

ACCEPTED BY THE DICKINSON COUNTY
SURVEY PEER GROUP AS THE OFFICIAL
CORNER UNDER MICHIGAN PUBLIC ACT
345 OF 1996 AT A MEETING HELD ON
12-17-96
RAF
COUNTY REPRESENTATIVE



Libor 7 Proo