

SURVEY & REMONUMENTATION

MAY 05 1997

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED

1996 DEC 18 AM 11:15

For corners of **COMMISSION**

<u>Dickinson</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>40N</u> R <u>29W</u>	<u>M-11*</u>
	T <u>40N</u> R <u>28W</u>	<u>A-11</u>
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

REGISTER OF DEEDS
DICKINSON COUNTY
IRON MOUNTAIN, MI 49801

13

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Michael Mileski, in a field survey on 6 November 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

1	A	B	C	D	E	F	G	H	I	J	K	L
2	6		5			4		3		2		1
3												
4	7		8			9		10		11		12
5												
6	18		17			16		15		14		13
7												
8	19		20			21		22		23		24
9												
10	30		29			28		27		26		25
11												
12	31		32			33		34		35		36
13												

A. Description of original monument and accessories and/or subsequent restoration:

M-11; Section Corner common to Sections 25 and 36, T40N, R29W;
See back of form.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

M-11; Section Corner common to Sections 25 and 36, T40N, R29W;
Found a 1" x 56" iron pipe with a 4" brass cap as set by Mr. Buckler in 1961 and in agreement with his new bearing trees as described in Part A. Replaced with a standard county monument described in Part C. Corner location falls 1 foot south of a 2 foot wide stream. Accepted as a careful and faithful reestablishment of the position of the original corner.

ACCEPTED BY THE DICKINSON COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON 12-17-96 BY ROP COUNTY REPRESENTATIVE

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-11; Section Corner common to Sections 25 and 36, T40N, R29W;
Set a 5/8" x 36" aluminum rod with a 3" aluminum cap stamped as to location

Set 7" spike	NW/side	8" White Spruce	N30°E	26.88'
Set 7" spike	S/side	5" Balsam	S66°E	49.45'
Set 7" spike	W/side	13" White Spruce	S14°W	76.97'
Set 7" spike	W/side	13" White Spruce	N06°W	57.64'
		Location Post	South	3.0'

All of the above new bearing trees are marked with upper and lower blazes. The lower blaze is scribed "NBT". Both blazes as well as a band around the tree at the upper blaze are painted red.

*This corner is also A-11 of T40N, R28W.



Signed by _____
Surveyor's Michigan License No. 39091

Date 3 Dec 1996
Bk. 17M pp 24 & 25