

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED

1998 DEC 16 PM 12:29

For corners in _____ Located in: _____ Corner Code # _____
 Dickinson _____ (County)

1. Public Land Survey T 40N R 28W F- 9
WAUCEDAH
 T _____ R _____
 T _____ R _____
 T _____ R _____
 T _____ R _____
 2. Property Controlling in Section S _____ T _____ R _____
 S _____
 T _____ R _____
 3. Miscellaneous S _____
 T _____ R _____
 Property in Sec. S _____
 T _____ R _____

REGISTER OF DEEDS
 DICKINSON COUNTY
 IRON MOUNTAIN, MICHIGAN

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, Robert R. Spear Jr., in a field survey on December 8, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

F-9: Quarter Corner Common to Sections 21 and 28.
1849: James Mullett, DS set Quarter Section Post. No description given as to its type. He established the following Bearing Trees:
 Cedar 6" N51E, 16 links
 Cedar 6" S86E, 29 links
1959: DNR random traverse notes indicate that a temporary marker was placed at 40.00 chains West of G-9.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1997: Coleman Engineering Survey crew searched area but found nothing during 1997 Dickinson County Remonumentation Program.
1998: Searched area but found nothing. Corner was established by proportionate measure on line between corners 1/2 mile East and West.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

F-9: 1998: Set a standard Dickinson County Survey monument, which became damaged due to underground interference about 3' below surface. Could not remove this so set another rod with cap stamped to identify the corner. Established the following accessories:

N55°E, 18.90' 8" Tamarack
 S75°E, 5.98' 8" Spruce
 S02°W, 6.17' 5" Spruce
 S88°W, 15.0' Orange carsonite survey marker
 N45°W, 15.0' Orange carsonite survey marker

Face, nail and butt blazes in all NBT's. Blazes are painted orange and all distances are to DH nails placed in tree.



ACCEPTED BY THE DICKINSON COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 845 OF 1990 AT A MEETING HELD ON 12-14-98

R. A. [Signature]
 COUNTY REPRESENTATIVE

Signed by Robert R. Spear Jr. Date 12-16-98
 Surveyor's Michigan License No. 43069

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS

JAN. 28, 1971
 REVISED MAY 14, 1975
 REVISED JAN., 1983
 REVISED OCT., 1995