

SURVEY &  
REMONUMENTATION

MAR 03 1998

RECORDED

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970/1997 DEC 12 PM 1:37

SECTION

For corners in

<u>Dickinson</u> (County)	Located In:	Corner Code #
Waucedah Township		
1. Public Land Survey	T40N R28W	<u>H-5</u>
	T ___ R ___	G-8
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

REGISTER OF DEEDS  
DICKINSON COUNTY  
RON MOORE, COUNTY CLERK

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, James H. Moore, in a field survey on October 15, 1997, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5								●					
6		10		17		16		15		14		13	
7													
8		19		20		21		●		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

H-5 - 1/4 corner common to Sections 10 and 15  
Post by James H. Mullett, D.S. 1849

Hemlock 15" S33°E 16 L.  
Hemlock 10" N47°E 33 L.

G-8 - 1/4 corner common to Sections 21 and 22  
Post by James H. Mullett, D.S. 1849

Sugar 12" S35°E 05 L.  
Sugar 14" \_\_\_\_\_

NOTED BY THE DICKINSON COUNTY  
SURVEY PEER GROUP AS THE OFFICIAL  
CORNER UNDER MICHIGAN PUBLIC ACT  
345 OF 1980 AT A MEETING HELD ON  
12-9-97

R.A.P.  
COUNTY REPRESENTATIVE

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

H-5 - found 1" galvanized pipe with 4" DNR stamped brass cap set at an existing corner location by B. Buckler in 1955 (old #13) 1955 bearing trees:

Y. Birch 12" N24°E 70 L.  
Hemlock 14" S81°E 58 L.

G-8 - found 1" galvanized pipe with 4" K. C. Corp. stamped aluminum cap set by proportionate measure in 1964 by N. Sperhake (old #1056) 1964 bearing trees:

Spruce 8" N84°W 61 L.  
Spruce 7" S60°E 34 L.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

H-5 - found above described monument in place  
New Witnesses:

S. Maple 5" S50°W (M.B.) 4.96' nail/tag  
S. Maple 6" S3°E (M.B.) 13.43' nail/tag  
S. Maple 7" N85°E (M.B.) 15.54' nail/tag  
S. Maple 7" N11°W (M.B.) 26.57' nail/tag

G-8 - found above described monument in place  
New Witnesses:

Balsam 5" N21°E (M.B.) 2.82' nail/tag  
Balsam 4" S89°E (M.B.) 5.46' nail/tag  
Balsam 5" S40°E (M.B.) 5.43' nail/tag  
Balsam 4" N67°W (M.B.) 10.5' nail/tag

placed carsonite marker N45°W 0.95'

placed carsonite marker North 0.85'

Signed by James H. Moore  
Surveyor's Michigan License No. 28423

Date 12-8-97

