

SURVEY &
REMONUMENTATION

MAR 03 1998

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED

1997 DEC 12 PM 1:37

For corners in

Dickinson Located in: Corner Code #
(County)
Waucedah Township
1. Public Land Survey T40N R 28W H-7
T___ R___ H-9
T___ R___
T___ R___
T___ R___
2. Property Controlling S___ T___ R___
in Section S___ T___ R___
3. Miscellaneous S___ T___ R___
Property in Sec. S___ T___ R___

REGISTER OF DEEDS
DICKINSON COUNTY
IRON MOUNTAIN, MICHIGAN

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, James H. Moore, in a field survey on October 14, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7								●					
8	19		20		21		22		23		24		
9								●					
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

H-7 - 1/4 corner common to Sections 15 and 22 Post by James H. Mullett, D.S. 1849
Cedar 12" N15°E 12 L.
Cedar 12" S01°W 10 L.

H-9 - 1/4 corner common to Sections 22 and 27 Post by James H. Mullett, D.S. 1849
Cedar 8" S17°E 05 L.
Cedar 10" N55°W 08 L.

ACCEPTED BY THE DICKINSON COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON 12-9-97

RJP
COUNTY REPRESENTATIVE

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

H-7 - found 1" pipe with 4" K.C. Corp. aluminum cap set by proportionate measure in 1964 by N. Spherhake (old #1052) 1964 bearing trees:
B. Ash 11" N10°W 20 L.
B. Ash 15" S51°W 52 L.

H-9 - found 1" pipe with 4" K.C. Corp. aluminum cap set by proportionate measure in 1964 by N. Spherhake (old #1053) 1964 bearing trees:
Cedar 5" S01°W 16-1/2 L.
Cedar 7" N11°E 52 L.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

H-7 - found above described monument in place New Witnesses:
B. Ash *18" S54°W (M.B.) 34.30' nail/tag
B. Ash *14" N05°W (M.B.) 12.98' nail/tag
W. Birch 6" N61°E (M.B.) 15.06' nail/tag
Pine 8" S26°E (M.B.) 15.55' nail/tag

H-9 - found above described monument in place New Witnesses:
Cedar 10" N40°E (M.B.) 21.60' nail/tag
Cedar 8" N05°W (M.B.) 19.50' nail/tag
Cedar 5" S28°E (M.B.) 5.00' nail/tag
Cedar *6" S06°W (M.B.) 11.55' nail/tag

placed carsonite mark South 1.0' placed carsonite marker South 1.1'

Signed by _____
Surveyor's Michigan License No. _____

Date 12-8-97

