

**SURVEY & REMONUMENTATION**

MAR 03 1998

**SECTION**

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

**RECORDED**

1997 DEC 12 PM 1:37

For corners in:

<u>Dickinson</u>	Located In:	Corner Code #
(County)		
Waucedah Township		
1. Public Land Survey	T40N R 28W	H-7
	T___ R___	H-9
	T___ R___	
	T___ R___	
2. Property Controlling in Section	S___ T___ R___	
	S___ T___ R___	
3. Miscellaneous Property in Sec.	S___ T___ R___	
	S___ T___ R___	

REGISTER OF DEEDS  
DICKINSON COUNTY  
IRON MOUNTAIN, MICHIGAN

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, James H. Moore, in a field survey on October 14, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7								●					
8	19		20		21		22		23		24		
9								●					
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

H-7 - 1/4 corner common to Sections 15 and 22  
Post by James H. Mullett, D.S. 1849

H-9 - 1/4 corner common to Sections 22 and 27  
Post by James H. Mullett, D.S. 1849

Cedar 12" N15°E 12 L.  
Cedar 12" S01°W 10 L.

Cedar 8" S17°E 05 L.  
Cedar 10" N55°W 08 L.

ACCEPTED BY THE DICKINSON COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON 12-9-97

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

H-7 - found 1" pipe with 4" K.C. Corp. aluminum cap set by proportionate measure in 1964 by N. Sperhake (old #1052) 1964 bearing trees:

H-9 - found 1" pipe with 4" K.C. Corp. aluminum cap set by proportionate measure in 1964 by N. Sperhake (old #1053) 1964 bearing trees:

B. Ash 11" N10°W 20 L.  
B. Ash 15" S51°W 52 L.

Cedar 5" S01°W 16-1/2 L.  
Cedar 7" N11°E 52 L.

COUNTY REPRESENTATIVE

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

H-7 - found above described monument in place  
New Witnesses:

H-9 - found above described monument in place  
New Witnesses:

B. Ash \*18" S54°W (M.B.) 34.30' nail/tag  
B. Ash \*14" N05°W (M.B.) 12.98' nail/tag  
W. Birch 6" N61°E (M.B.) 15.06' nail/tag  
Pine 8" S26°E (M.B.) 15.55' nail/tag

Cedar 10" N40°E (M.B.) 21.60' nail/tag  
Cedar 8" N05°W (M.B.) 19.50' nail/tag  
Cedar 5" S28°E (M.B.) 5.00' nail/tag  
Cedar \*6" S06°W (M.B.) 11.55' nail/tag

placed carsonite marker South 1.0'  
\*Existing

placed carsonite marker South 1.1'

Signed by \_\_\_\_\_  
Surveyor's Michigan License No. \_\_\_\_\_

Date 12-8-97

