

SURVEY & REMONUMENTATION

MAY 07 1997

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED

1996 DEC 18 AM 11:17

For corners in DICKINSON
 (County)

Located In:

Corner Code #

WAUCEDAH TWP.

- | | | |
|--------------------------------------|---------------------------|------------|
| 1. Public Land Survey | T <u>40N</u> R <u>28W</u> | <u>J-5</u> |
| | T _____ R _____ | <u>K-2</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

REGISTER OF DEEDS
 DICKINSON COUNTY
 IRON MOUNTAIN, MI 49801

13

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, ROBERT F. PERKINS, in a field survey on 10-8, 19 96, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

J-5 $\frac{1}{4}$ CORNER COMMON TO SECTIONS ¹¹ T4
 POST BY J. H. MULLETT, D.S. 1849
 ORIGINAL BEARING TREES
 IRONWOOD 8" N08°W 11 L.
 ELM 4" S85°E 05 L.

K-2 $\frac{1}{4}$ CORNER COMMON TO SECTIONS 2/1
 POST BY J. H. MULLETT, D.S. 1849
 ORIGINAL BEARING TREES
 W. PINE 14" N69°E 30 L.
 W. PINE 24" S61°W THE DICKINSON COUNTY
 ACCEPTED ABOVE LOCATION SURVEY PIER GROUP AS THE OFFICIAL
 CORNER UNDER MICHIGAN PUBLIC ACT
 345 OF 1990 AT A MEETING HELD ON
10-12-96
R.F.P.
 COUNTY REPRESENTATIVE

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

J-5 1913 M.J. BACCO WITNESSES CORNER
 MAPLE 6" S12°E 31.3'
 MAPLE 8" N56°E 49.0'
 HEMLOCK 8" N33°E 41.3'
 10-8-96 FIND $\frac{1}{2}$ " RE-ROD AND REMAINS
 OF ORIGINAL ELM BT NOW A STUMP \pm 30".
 LOWER BLAZE VISIBLE. ALSO FIND ALL 3
 STUMP HOLES OF BACCO BT'S. HEAVY BLAZED
 LINE RUNS EAST-WEST. PAINT LINE RUNS
 NORTH. 2 NEWER VISIBLE BT'S EVIDENT.

K-2 FOUND $1\frac{1}{2}$ " IRON PIPE FLUSH WITH GROUND.
 ALSO $1\frac{1}{2}$ " IRON PIPE ALONG SIDE PROJECTING 18".
 ANCIENT FENCE LINE RUNS SOUTH FROM CORNER.
 DISTANCE CHECKS WITH GLO CALL NORTH TO
 STURGEON RIVER.
 R. CAZZOLA, ADJOINING PROPERTY OWNER,
 STATED HE HAD PERSONAL KNOWLEDGE OF CORNER
 BEING IN EXISTENCE OVER 50 YEARS.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

J-5 ACCEPTED ABOVE LOCATION.
 PLACES D.C. REMON. $2\frac{1}{2}$ " STAMPED MONUMENT
 AT RE-ROD.
 NEW BEARING TREES:
 MAPLE 8" S34°E (M.B.) 18.30' NAIL/TAG
 MAPLE 12" S78°W (M.B.) 13.20' NAIL/TAG
 LYNN 10" S40°W (M.B.) 23.21' NAIL/TAG
 LYNN 10" N38°E (M.B.) 30.20' NAIL/TAG
 ELM STUMP 30" S85°E (M.B.) 3.0' (BT)
 SET CARSONITE MARKER 1.2' N.W. OF CORNER

K-2 ACCEPTED ABOVE DESCRIBED IRON PIPE
 AS BEST AVAILABLE EVIDENCE OF CORNER
 LOCATION. PLACED $2\frac{1}{2}$ " STAMPED D.C.
 REMON. MONUMENT INSIDE EXISTING IRON PIPE.
 NEW BEARING TREES:
 SPRUCE 7" S45°E (M.B.) 14.24' NAIL/TAG
 SPRUCE 4" N48°E (M.B.) 24.64' NAIL/TAG
 SPRUCE 18" N71°E (M.B.) 39.67' NAIL/TAG
 W.PINE 3" N28°W (M.B.) 82.95' NAIL/TAG
 PLACED CARSONITE MARKER 1' EAST OF CORNER.

Signed by Robert F. Perkins
 Surveyor's Michigan License No. 12027

Date NOVEMBER 6, 1996

