

MAY 07 1997

RECORDED

1996 DEC 18 AM 11:17

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in DICKINSON
(County)
WAUCEDAH TWP.

Located In:

Corner Code #

- 1. Public Land Survey T 40N R 28W M-1
T _____ R _____ K-1
T _____ R _____
T _____ R _____
- 2. Property Controlling in Section S _____ T _____ R _____
S _____ T _____ R _____
- 3. Miscellaneous Property in Section S _____ T _____ R _____
S _____ T _____ R _____

REGISTER OF DEEDS
DICKINSON COUNTY
IRON MOUNTAIN, MI 49801

21

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L
2	6	5	4	3	2						
3											
4	7	6	9	10	11	12					
5											
6	16	17	16	15	14	13					
7											
8	19	20	21	22	23	24					
9											
10	30	29	28	27	26	25					
11											
12	31	32	33	34	35	36					
13											

I, ROBERT F. PERKINS, in a field survey on 10-15, 1996, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

M-1 NORTHEAST CORNER SECTION 1, T40N-R28W (CLOSING CORNER)
POST BY J. H. MULLETT, D.S. 1848
ORIGINAL BEARING TREES
CEDAR 12" S55°E 12 L.
CEDAR 15" S79°W 23 L.

K-1 NORTHWEST CORNER SECTION 1, T40N-R28W (CLOSING CORNER)
POST BY J. H. MULLETT, D.S. 1849
ORIGINAL BEARING TREES
HEMLOCK 10" S48°W 19 L.
SUGAR 14" S25°E 30 L.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

M-1 FOUND 4" SCRIBED CEDAR POST. ALSO FOUND POINT OF SMALLER OLDER POST ALONG SIDE (POSSIBLE ORIGINAL).
FOUND CEDAR 11" SCRIBED "B.T."

K-1 NO EVIDENCE OF ORIGINAL CORNER OR ACCESSORIES FOUND. PLACED CORNER ON 4TH. CORRECTION LINE AT PROJECTION OF ANCIENT FENCE LINE SOUTH, 1016' EAST OF STANDARD CORNER TO WEST (GLO DISTANCE IS 1023').
THE ABOVE LOCATION FALLS APPROXIMATELY IN OLD EAST-WEST FENCE LINE ACCEPTED BY THE DICKINSON COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON

12-17-96
RFP
COUNTY REPRESENTATIVE

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-1 SET 3/4" STAMPED D.C. REMON. CORNER ON 4TH CORRECTION LINE 2.30' NORTH OF ABOVE FOUND POST.
NEW BEARING TREES:
CEDAR 6" N58°W (M.B.) 7.22' NAIL/TAG
CEDAR 9" N27°E (M.B.) 23.55' NAIL/TAG
CEDAR 6" S45°E (M.B.) 13.73' NAIL/TAG
CEDAR 11" S31°W (M.B.) 8.15' EXISTING B.T.
PLACED CARSONITE STAKE 0.5' NORTH OR CORNER.

K-1 SET 3/4" STAMPED D.C. REMON. CORNER AT ABOVE DEESCRIBED LOCATION.
NEW BEARING TREES:
HEMLOCK 24" S67°W (M.B.) 109.30' NAIL/TAG
MAPLE 40" S46°W (M.B.) 111.62' NAIL/TAG
MAPLE 16" S52°W (M.B.) 151.14' NAIL/TAG
W. PINE 10" S12°W (M.B.) 89.11' NAIL/TAG
PLACED CARSONITE MARKER 1.0' EAST.

Signed by Robert F. Perkins
Surveyor's Michigan License No. 12027

Date NOVEMBER 6, 1996

