

MAY 07 1997

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED

1996 DEC 18 AM 11:17

For corners in DICKINSON (County)

Located In:

Corner Code #

WAUCEDAHP TWP.

REGISTER OF DEEDS DICKINSON COUNTY IRON MOUNTAIN, MI 49801

- 1. Public Land Survey T 40N R 28W K-7 K-8
2. Property Controlling in Section S T R
3. Miscellaneous Property in Section S T R
4. Lot No. , Recorded Plat
5. Private Claims

23

Register of Deeds Stamp & File Number

Grid table with columns A-L and rows 1-13. Contains numerical data and two black dots in the grid.

I, ROBERT F. PERKINS, in a field survey on 10-23, 1996, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

K-7 CORNER COMMON TO SECTIONS 13-14-23-24 POST BY J. H. MULLETT, D.S. 1849 ORIGINAL BEARING TREES W. PINE 14" S18°E 30 L. Y. PINE 28" S64°W 21 L.

K-8 1/4 CORNER COMMON TO SECTIONS 23-24 POST BY J. H. MULLETT, D.S. 1849 ORIGINAL BEARING TREES FIR 6" S78°E 26 L. Fir 4" N29°W 56 L.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

K-7 FOUND 1" IRON PIPE WITH 4" D.N.R. BRASS CAP SET BY B. BUCKLER IN 1960 (#421) AT OLD WOOD STAKE AND IRON BAR. 1960 BEARING TREES SPRUCE 10" S77°E (M.B.) 89 L. (FOUND) BALSAM 7" N35°E (M.B.) 40 L. MAPLE 5" N65°W (M.B.) 39 L. (FOUND)

K-8 FOUND 1" IRON PIPE WITH 4" D.N.R. BRASS CAP SET BY B. BUCKLER AT FOUND IRON PIPE AND WOOD POST IN 1960 (#334). 1960 BEARING TREES B. ASH 9" N78°W 63 L. S. MAPLE 4" S18°E 15 L.

ACCEPTED BY THE DICKINSON COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1980 AT A MEETING HELD ON 12-17-96 RFP COUNTY REPRESENTATIVE

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-7 ACCEPTED ABOVE DESCRIBED MONUMENT NEW BEARING TREES: MAPLE 9" N88°E (M.B.) 32.48' NAIL/TAG MAPLE 12" N65°W (M.B.) 25.44' OLD B.T. SPRUCE 20" S73°E (M.B.) 58.95' OLD B.T. PINE STUMP S72°W (M.B.) 9.0' PLACED CARSONITE MARKER 1.0' NORTH OF EXISTING CORNER.

K-8 ACCEPTED ABOVE DESCRIBED MONUMENT. NEW BEARING TREES: B. ASH 12" N76°W (M.B.) 41.65' OLD B.T. S. MAPLE 12" S62°E (M.B.) 15.23' NAIL/TAG FIR 4" N28°E (M.B.) 17.2' NAIL/TAG FIR 5" N13°W (M.B.) 20.12' NAIL/TAG SET CARSONITE STAKE 1.0' NORTH OF EXISTING CORNER.

Signed by [Signature]

Date NOVEMBER 6, 1996

Surveyor's Michigan License No. 12027

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS JAN 1983 REVISED 1987

