

MAY 07 1997

COMMISSION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED  
1996 DEC 18 AM 11:17

For corners in

DICKINSON  
(County)  
WAUCEDAHP TWP.

Located In:

Corner Code #

- 1. Public Land Survey T 40N R 28W
- T \_\_\_\_\_ R \_\_\_\_\_
- T \_\_\_\_\_ R \_\_\_\_\_
- T \_\_\_\_\_ R \_\_\_\_\_
- 2. Property Controlling S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
- in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
- 3. Miscellaneous S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
- Property in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

L-7  
K-6

REGISTER OF DEEDS  
DICKINSON COUNTY  
IRON MOUNTAIN, MI 49801

19

Register of Deeds Stamp & File Number

- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

I, ROBERT F. PERKINS, in a field survey on 10-24, 19 96, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

L-7  $\frac{1}{4}$  CORNER COMMON TO SECTIONS <sup>13</sup> 24  
POST BY J. MULLETT, D.S. 1849  
ORIGINAL BEARING TREES  
BIRCH 3" S8°E 07 L.  
LYNN 14" N22°E 13 L.

K-6  $\frac{1}{4}$  CORNER COMMON TO SECTION 14/13  
POST BY J. H. MULLETT, D.S. 1849  
ORIGINAL BEARING TREES  
TAMARACK 8" S18°E 11 L.  
TAMARACK 8" S88°W 06 L.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

L-7 NO EVIDENCE OF ORIGINAL CORNER OR ACCESSORIES FOUND.  
FOUND 1" IRON PIPE WITH 4" D.N.R. BRASS CAP SET BY B. BUCKLER 2-23-1960 BT PROPORTIONATE MEASURE.  
1960 BEARING TREES  
HARD MAPLE 9" S13°E 65½ L.  
HARD MAPLE 8" S88°E 64½ L.

K-6 FOUND OLD SQUARE CEDAR POST WITH REMAINS OF MUCH OLDER POST DOWN.  
FOUND CEDAR 18" WITH VISIBLE SCRIBING N31°W (M.B.) 20.62' BRUSHED LINE RUNS EAST AND WEST AND PAINT LINE RUNS SOUTH FROM POST.  
GLO CALL LEAVE SWP. 42.00' CHECKS WELL.

ACCEPTED BY THE DICKINSON COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON

12-17-96  
RF

COUNTY REPRESENTATIVE

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

L-7 FOUND ABOVE DESCRIBED MONUMENT AND BEARING TREES IN PLACE.  
NEW BEARING TREES:  
HEMLOCK 16" S69°W (M.B.) 20.80' NAIL/TAG  
DBL. BEECH 6" N10°E (APPROX.) 26.92' NAIL/TAG  
S. MAPLE 12" S88°E (M.B.) 42.50' OLD B.T.  
S. MAPLE 12" S10°E (M.B.) 43.05' OLD B.T.  
PLACED CARSONITE WITNESS STAKE ± 1.0' SOUTH.

K-6 ACCEPTED ABOVE POST AS BEST AVAILABLE EVIDENCE OF CORNER LOCATION.  
SET 3½" STAMPED D.C. REMON. CORNER AT POST.  
NEW BEARING TREES:  
CEDAR 18" N31°W (M.B.) 20.62' OLD B.T.  
CEDAR 20" N12°E (M.B.) 11.80' OLD B.T.  
CEDAR 12" S60°W (M.B.) 31.30' NAIL/TAG  
B. SPRUCE 6" S26°E (M.B.) 25.62' NAIL/TAG  
PLACED CARSONITE MARKER 1.0' NORTH OF OLD CORNER.

Signed by Robert F. Perkins

Date NOVEMBER 6, 1996

Surveyor's Michigan License No. 12027

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971  
REVISED MAY 18, 1982  
REVISED JAN. 1985

