

SURVEY & REMONUMENTATION

MAR 03 1998

RECORDED

SECTION

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970 1997 DEC 12 PM 1:37

For corners in

<u>Dickinson</u> (County)	Located in:	Corner Code #
<u>Waucedah Township</u>	<u>T40N R 28W</u>	<u>L-13</u>
1. Public Land Survey	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

REGISTER OF DEEDS
DICKINSON COUNTY
RON MOORE, COUNTY REPRESENTATIVE

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, James H. Moore, in a field survey on September 22, 19 97 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

L-13 - 1/4 corner common to Section 36, T40N-R28W and Section 1, T39N-R28W
Post by H. Brevoort, D.S. 1848

Birch	12"	N18°E	17 L.
Birch	10"	N67°W	09 L.

ACCEPTED BY THE DICKINSON COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON 12-9-97

R.M.P.
COUNTY REPRESENTATIVE

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

L-13 - found 1" pipe with 4" K.C. Corp. aluminum cap set by proportionate measure in 1966 by E. Kazianka (old #1034)

1966 bearing trees:

Cedar	9"	N09°W	8 L.
Cedar	7"	S42°W	29-1/2 L.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

L-13 - found above described monument in place
New Witnesses:

Cedar	11"	S63°E (M.B.)	41.40' nail/tag
Cedar	*11"	N02°W (M.B.)	4.95' nail/tag
Cedar	*10"	S44°W (M.B.)	19.50' nail/tag
Spruce	10"	S82°W (M.B.)	16.53' nail/tag

placed carsonite monument East 0.83' this corner of Section 36, T40N-R28W

*Existing B.T.

Signed by James H. Moore
Surveyor's Michigan License No. 342

Date 12-8-97

