

MAR 03 1998

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED

1997 DEC 12 PM 1:37

For corners in

<u>Dickinson</u> (County) Waucedah Township	Located in:	Corner Code #
1. Public Land Survey	T40N R28W	L-9 M-9
	T___ R___	_____
	T___ R___	_____
	T___ R___	_____
2. Property Controlling in Section	S___ T___ R___	_____
	S___ T___ R___	_____
3. Miscellaneous Property in Sec.	S___ T___ R___	_____
	S___ T___ R___	_____

REGISTER OF DEEDS
DICKINSON COUNTY
(RON MULLETT, CLERK)

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, James H. Moore, in a field survey on September 23, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

L-9 - 1/4 corner common to Sections 24 and 25
Post by James H. Mullett, D.S. 1849

M-9 - corner common to Sections 24 and 25,
T40N-R28W and Section 19 and 30, T40N-R27W
Post by James H. Mullett, D.S. 1849

Cedar 14" S55°W 04 L.
Fir 10" N88°E 16 L.

Lynn 15"
Sugar 12"

ACCEPTED BY THE DICKINSON COUNTY
SURVEY PARTY GROUP AS THE OFFICIAL
CORNER UNDER MICHIGAN PUBLIC ACT
345 OF 1990 AT A MEETING HELD ON
12-9-97

ROP
COUNTY REPRESENTATIVE

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

L-9 - found 1" pipe with 4" K.C. Corp.
cap set by proportionate measure
in 1966 by E. Kazianka (old #1025)
1966 bearing trees:

Cedar 7" N44°E 21-1/2 L.
Cedar 5" S23°W 14 L.

M-9 - found 4" pipe DNR cap on 3" x 3" post
(originally a 1" pipe) set by proportionate
measure in 1959 by B. Buckler (old #331)
1959 bearing trees:

S. Maple 5" N11°E 11 L.
B. Cherry 8" S72°E 70 L.
W. Birch 7" S78°W 44-1/2 L.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

L-9 - found above described monument in place
New Witnesses:

Aspen 18" S72°W (M.B.) 5.15' nail/tag
Cedar 7" N18°W (M.B.) 19.90' nail/tag
Cedar *8" S18°W (M.B.) 9.12' nail/tag
Cedar *11" N48°E (M.B.) 14.11' nail/tag

M-9 - found above described monument in correct location
as verified from existing bearing trees
New Witnesses:

S. Maple *12" N25°E (M.B.) 7.42' nail/tag
Balsam 6" S04°E (M.B.) 6.58' nail/tag
W. Birch *14" S83°W (M.B.) 28.83' nail/tag
Maple 6" N46°W (M.B.) 47.52' nail/tag

placed carsonite marker South 1.3'
this corner is also A-9 of T40N-R27W

placed carsonite marker South 1.2'
this corner is also A-9 of T40N-R27W

Signed by _____
Surveyor's Michigan License No. 28423

Date 12-8-97

