

✓

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 40 NR. 28 W.
T. 41 NR. 28 W.

----- Dickinson ----- COUNTY

DESCRIPTION OF CORNER Section Corner common to Sections 4, 5, 35 -----

DESCRIPTION OF CORNER MONUMENT 1" Pipe with 4" Brass cap -----

WITNESSES TO CORNER 6" W. Birch - S 55 E - 17 Links -----

8" Tamarack - N 27 W - 42 Links -----

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was established, by proportionate measurement, by Forestry Division survey crew, while making a partial resurvey of this area. Good corner 16.70 ch. West, good Line Tree 30 ch. East, as per Gov't. notes. One probable original B.T. in place, badly rotted.

Corner was placed and witnessed July 21, 1954.

SURVEYORS SEAL

SIGNED Alan C. DeWalter DATE 2/11/55
REGISTERED LAND SURVEYOR