

# LAND CORNER RECORDATION CERTIFICATE

## FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____ T. <u>40</u> <sup>N.</sup> <del>X</del> , R. <u>28</u> <sup>W.</sup> <del>X</del>		G1 & H1
2. PROPERTY CONTROLLING IN SECTION _____, T. _____, R. _____	N. S., R. _____	
3. MISCELLANEOUS PROPERTY IN SECTION _____, T. _____, R. _____	N. S., R. _____	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Arthur O. Enger, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on see below, 19\_\_\_\_, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_, 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

**A. Description of original monument and accessories and/or subsequent restoration:**

**Corner H1 (North 1/4 Corner of Sec. 3, T40N, R28W):**  
 Not established in original survey nor subsequently, apparently.

**Corner G1 (Northwest Corner of Sec. 3, T40N, R28W):**  
 Wood post (Not found. Found 1" I.D. iron pipe with 4" brass cap in place)  
 Hemlock 10 S62E 28 (Not found. Found Sugar Maple 5 S64E 41 NBT)  
 Cedar 14 S58W 14 ( " " Found Sugar Maple 5 S12W 40 NBT)

**B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:**

**Corner G1:** Found existing monument to be 2.14 feet north of true line upon which it is supposed to close. Did not disturb this monument, but on 6/26/75 placed another monument described below to mark the true closing point. Existing monument set by B. D. Buckler, R. L. S. on 3/11/59, by proportionate measurement.

**Corner H1:** Established 6/27/75 proportionately on 4th Correction Line between Standard Corner 31 & 36, T41N, R28W 1506.96 feet E and Standard Corner 35 & 36, T41N, R28W 3776.10 feet W. Corner thus established is at mid-point of line between closing sec. corners 2666.66 feet to E and to W.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

**Corner G1:** 1" I.D. by 12" iron pipe set 2.14 ft. S of 1" iron pipe w/brass cap.

No new witnesses.

**Corner H1:** 1" I.D. x 36" iron pipe with 3 1/2" aluminum cap.  
 Cedar 5 S39°W (mag.) 8.5 ft. "1/4S, BT"  
 Cedar 8 N30°E (mag.) 21.0 ft. "1/4S, BT"

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

APPROVED AND SIGNED BY Arthur O. Enger DATE January 28, 1976  
CHIEF OF SURVEY PARTY  
MICHIGAN REGISTERED LAND SURVEYOR

Arthur O. Enger  
 Michigan Department of Natural Resources  
 SURVEYOR'S MICHIGAN REGISTRATION NO. 13581

