

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY_____ T. <u>40</u> ^{N.} XX R. <u>28</u> ^{W.} XX		<u>B13</u>
2. PROPERTY CONTROLLING IN SECTION <u>31</u> , T. <u>40</u> ^{N.} XX R. <u>28</u> ^{W.} XX		<u>15 & 16</u>
3. MISCELLANEOUS PROPERTY IN SECTION _____ , T. _____ ^{N.} R. _____ ^{E.} W.		
4. LOT NO. _____ , RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Arthur O. Enger do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were, in a field survey on see below 19___, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____ 19___, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

Corner B13: Wood post Not found. No subsequent monuments found.
 Pine 6 N71°E 12 Not found. No subsequent accessories found.
 Pine 4 N 8°W 7 Not found. No subsequent accessories found.

Corner 15 & 16: Not established in original survey; Corner 15 probably had been established at least approximately, as it falls near an E & W old field edge. No evidence that Corner 16 had been established previously.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Corner B13: Re-established 6/19/73 proportionately on line between section corners 39.994 ch. E and 36.488 ch. W.

Corner 15: Established 6/19/73 proportionately on line between 1/4 corner 19.997 ch. E and section corner 16.491 ch. W. A meandering E & W fence line is 22 ft. N of corner.

Corner 16: Established 6/18/73 proportionately on line between section corner 19.997 ch. E and 1/4 corner 19.997 ch. W. Corner falls about on W margin of swamp, course SW and NE.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Monuments for all three corners: 1" I.D. x 36" iron pipe with 4" aluminum cap.

Witnesses for Corner B13: W. Birch 6 S16½°E (mag.) 70.4 ft. "1/4S, NBT"
 Red Maple 5 S19°W (mag.) 71.0 ft. "1/4S, NBT"

Corner in beaver flooded area, in water 2-3 ft. deep.

Witnesses for Corner 15: W. Spruce 7 N21½°E (mag.) 36.0 ft. "1/16S, BT"
 Balsam 4 N66½°W (mag.) 82.7 ft. "1/16S, BT"

Witnesses for Corner 16: Cherry 12 N64°W (mag.) 50.0 ft. "1/16S, BT"
 Aspen 9 N1°E (mag.) 36.1 ft. "1/16S, BT"

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Arthur O. Enger DATE January 31, 1974

Arthur O. Enger
 Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 13581

