

# LAND CORNER RECORDATION CERTIFICATE

## FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

| FOR CORNERS OF--                           | LOCATED IN--  | CORNER CODE NUMBER       |
|--|---|--------------------------|
| 1. PUBLIC LAND SURVEY _____                | T. <u>40</u> N. <u>XX</u> R. <u>28</u> W. <u>XX</u>     | <u>C13; D13; and E13</u> |
| 2. PROPERTY CONTROLLING IN SECTION _____   | , T. _____ N. _____ S. _____ R. _____ E. _____ W. _____ | _____                    |
| 3. MISCELLANEOUS PROPERTY IN SECTION _____ | , T. _____ N. _____ S. _____ R. _____ E. _____ W. _____ | _____                    |
| 4. LOT NO. _____, RECORDED PLAT _____      |   |                          |
| 5. PRIVATE CLAIMS _____                    |   |                          |

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Arthur O. Enger do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram—over) were, in a field survey on see below 19\_\_\_\_, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_ 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

**A. Description of original monument and accessories and/or subsequent restoration:**

|                              |            |                                  |
|------------------------------|------------|----------------------------------|
| <b>Corner C13:</b> Wood post | Not found. | No subsequent monuments found.   |
| W. Pine 14 N56W 37           | Not found. | No subsequent accessories found. |
| Birch 14 N75E 17             | " "        | " "                              |
| <b>Corner D13:</b> Wood post | Not found. | No subsequent monuments found.   |
| Cedar 14 N70E 16             | " "        | No subsequent accessories found. |
| Cedar 12 N27W 13             | " "        | " "                              |
| <b>Corner E13:</b> Wood post | Not found. | No subsequent monuments found.   |
| W. Pine 20 N57E 23           | " "        | " accessories found.             |
| W. Pine 36 N 6W 44           | " "        | " "                              |

**B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:**

**Corner C13:** Re-established 6/18/73 proportionately on line between section corners 76.482 ch. W and 159.964 ch. E. Distances W to rock ledge, swamp edge, and stream agree closely with original field notes.

**Corner D13:** Re-established 6/15/73 proportionately on line between section corners 116.473 ch. W and 119.981 ch. E. Distances to natural features mentioned in original field notes check well in latitude, and substantially so in departure.

**Corner E13:** Re-established 6/20/73 proportionately on line between section corners 156.464 ch. W and 79.990 ch. E. Substantial agreement with original field note calls to natural features is found on line going 20 ch. N from the corner point.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

**Witnesses for Corner C13:** Red Pine 9 S39<sup>0</sup>W (mag.) 15.6 ft. "S 6, NBT"  
 J. Pine 8 N54<sup>0</sup>W (mag.) 16.8 ft. "S31, NBT"  
 W. Pine 7 N43<sup>0</sup>E (mag.) 52.5 ft. "S32, NBT"

Also squared and scribed a 4" red pine N25<sup>0</sup>W 4.8 ft. from corner.

**Witnesses for Corner D13:** Cedar 6 S26<sup>0</sup>E (mag.) 16.7 ft. "1/4S, NBT"  
 Cedar 6 N57<sup>0</sup>W (mag.) 6.8 ft. "1/4S, NBT"

Also squared and scribed a 4" cedar N21<sup>0</sup>E 1.7 ft. from corner.

**Witnesses for Corner E13:** W. Spruce 5 N76<sup>0</sup>W (mag.) 36.4 ft. "S32, NBT"  
 W. Spruce 10 S46<sup>0</sup>E (mag.) 36.8 ft. "S4, NBT"  
 R. Maple 6 S27<sup>0</sup>W (mag.) 14.0 ft. "S5, NBT"

**Monuments for all three corners:** 1" I.D. x 36" iron pipe with 4" aluminum cap.

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

APPROVED AND SIGNED BY Arthur O. Enger DATE January 31, 1974

**Arthur O. Enger**  
 Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 13581

