

# LAND CORNER RECORDATION CERTIFICATE

## FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY_____	T. <u>40</u> N. <del>XX</del> R. <u>28</u> <del>XX</del> W.	<u>F13 &amp; G13</u>
2. PROPERTY CONTROLLING IN SECTION_____	, T. _____ N. _____ S. _____ R. _____ E. _____ W. _____	_____
3. MISCELLANEOUS PROPERTY IN SECTION_____	, T. _____ N. _____ S. _____ R. _____ E. _____ W. _____	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Arthur O. Enger do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram—over) were, in a field survey on June 20, 1973 ~~1973~~, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_ 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

**A. Description of original monument and accessories and/or subsequent restoration:**

<b>Corner F13:</b> Wood post	Not found. No subsequent monuments found.
Cedar 10 N68E 9	Not found. No subsequent accessories found.
Cedar 8 S32W 18	" " " " " "
<b>Corner G13:</b> Wood post	Not found. No subsequent monuments found.
W. Pine 34 N34E 20	Hummocks of long-overturned trees found.
W. Pine 18 S6E 26	" " " " " "
W. Pine 28 N64W 31	Found

**B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:**

**Corner F13:** Re-established proportionately on line between section corners 196.455 ch. W and 39.999 ch. E. Corner falls on side of a granite dome, on rock as implied in original field notes.

**Corner G13:** Re-established from pieces of overgrown notched axe blaze on remains of original BT, now in very poor condition. Position checks closely with distances to, and alignment with, corners on township line 3 miles W and 2 miles E. Hummocks of long-overturned trees found in positions corresponding to two other original BT's.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

**Monuments for both corners:** 1" I.D. x 36" iron pipe with 4" aluminum cap.

**Witnesses for Corner F13:** Cedar 6 N54½°E (mag.) 8.8 ft. "1/4S, NBT"  
Cedar 7 S9°E (mag.) 17.8 ft. "1/4S, NBT"

**Witnesses for Corner G13:** Red Maple 7 S71°W (mag.) 50.5 ft. "S4, NBT"  
Red Maple 6 N31°W (mag.) 44.0 ft. "S33, NBT"  
Red Maple 6 N77½°E (mag.) 28.7 ft. "S34, NBT"

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

APPROVED AND SIGNED BY Arthur O. Enger DATE January 31, 1974

**Arthur O. Enger**  
Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 13581

