

# LAND CORNER RECORDATION CERTIFICATE

## FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>40</u> N. <u>XX</u> R. <u>28</u> <u>XX</u> W.	<u>H13 &amp; I13</u>
2. PROPERTY CONTROLLING IN SECTION <u>34</u>	T. <u>40</u> N. <u>XX</u> R. <u>28</u> <u>XX</u> W.	<u>16</u>
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. _____ R. _____ E. _____ W. _____	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Arthur O. Enger do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were, in a field survey on June 21 1973, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_ 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

- A. Description of original monument and accessories and/or subsequent restoration:
- Corner H13: Wood Post Not found. No subsequent monuments found.
  - W. Pine 14 N52W 30 Not found. No subsequent accessories found.
  - Sugar 6 N18W 37 " " " " " "
  - Corner I13: Wood post Not found.
  - Lynn 10 N40E 21 Not found. No subsequent accessories found.
  - W. Pine 14 N38W 17 Not found. " " " "

Found a 1" I.D. x 41" iron pipe lying on ground, with flattened point end bearing N27½° E 6.4 ft. from corner position reported herein, but could not determine where it had been on the ground.

Corner 16: Not established in original survey nor subsequently, apparently.

- B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:
- Corner H13: Re-established proportionately on line between section corners 40.071 ch. to W and 120.213 ch. to E.
  - Corner I13: Re-established proportionately on line between section corners 80.142 ch. E and 80.142 ch. W. Corner falls 1.25 ch. N of river edge (record distance is 1.20 ch.)
  - Corner 16: Established on line between section corner 20.035 ch. E and 1/4 corner 20.035 ch. W.

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
- Monuments for all three corners: 1" I.D. x 36" iron pipe with 4" aluminum cap.
  - Witnesses for Corner H13: W. Pine 12 S38½° E (mag.) 11.0 ft. "1/4S, NBT"
  - Cedar 7 S71° W (mag.) 35.4 ft. "1/4S, NBT"
  - Witnesses for Corner I13: Cedar 12 S54½° W (mag.) 24.6 ft. "S3, NBT"
  - Cedar 6 N52½° W (mag.) 57.5 ft. "S34, NBT"
  - Elm 5 N7° E (mag.) 16.8 ft. "S35, NBT"
  - Witnesses for Corner 16: Sugar Maple 3 S55° E (mag.) 37.2 ft. "1/16S, BT"
  - W. Spruce 5 N87° E (mag.) 39.7 ft. "1/16S, BT"
- Note: At this corner, monument slants to S because of large rock at point.  
Punch mark on cap is the corner point.

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

APPROVED AND SIGNED BY Arthur O. Enger DATE January 31, 1974  
CHIEF OF SURVEY PARTY  
MICHIGAN REGISTERED LAND SURVEYOR

**Michigan Department of Natural Resources**

SURVEYOR'S MICHIGAN REGISTRATION NO. 13581

