

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 40 N.R. 28 W


Dickinson COUNTY

DESCRIPTION OF CORNER Section Corner for Secs. 5-6-7-8

CORNER MONUMENT 1" Ir on Pipe with 4" Aluminum Cap

DATE MONUMENT PLACED AND WITNESSED 5/24/65 Bray and Hinds

WITNESSES TO CORNER..... 10" Elm (S7 NBT), S 60° W, 30½ lks.



8" H. Maple (S6 NBT), N 30° W, 33½ lks.

6" H. Maple (S5 NBT), N 58° E, 09 lks.

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This Corner was set at location of point of old down post which checks fairly well with 1/4 Corners to East and West and Stream and Section Corner to North.

No original evidence found.

SURVEYOR'S SEAL

Frank J. Bray
SIGNED Frank J. Bray DATE 6/8/1965
REGISTERED LAND SURVEYOR