

MICHIGAN  
DEPARTMENT OF CONSERVATION  
FORESTRY DIVISION

LAND CORNER RECORD

T. 40 N.R. 28 W


Dickinson COUNTY

DESCRIPTION OF CORNER Section corner for Secs. 7-8-17-18

CORNER MONUMENT 1" Iron Pipe with 4" Aluminum Cap

DATE MONUMENT PLACED AND WITNESSED 5/28/63 Bray and Hinds

WITNESSES TO CORNER..... 6" W. Birch (S7 NBT), N 85° W, 13½ Lks.



12" Spruce (S8 NBT), N 69° E, 04 Lks.

7" W. Birch (S17 NBT), S 61° E, 21 Lks.

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This Corner was re-established by double proportioned measurement between Section Corners 1 mile to South, East and North and Stream crossing to West.

No original evidence.

SURVEYOR'S SEAL

SIGNED Frank J. Bray DATE 6/8/1965  
REGISTERED LAND SURVEYOR