

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 40. NR. 28 W. . .

----- Dickinson ----- COUNTY

DESCRIPTION OF CORNER $\frac{1}{4}$ corner between sections 27 and 28 -----

DESCRIPTION OF CORNER MONUMENT 1" pipe with 4" brass cap. -----

WITNESSES TO CORNER Black Ash (twin) 6" N 40 E 50 links
marked $\frac{1}{4}$ S NBT -----

----- Hemlock ----- 14" S 72 E ----- 48 $\frac{1}{2}$ links -----
marked $\frac{1}{4}$ S NBT -----

----- Cedar ----- 18" N 82 E ----- 58 links -----
marked $\frac{1}{4}$ S NBT -----

Distances measured from center of brass cap to NBT notch.

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR
RESTORED.

This corner pointed out to me by Norman J. Karsten, Assistant District Forester.

Corner was replaced from one probable original Hemlock bearing tree in fair condition.
Tree down, with BT and description blaze plain. No scribe marks evident, but axe
marks plain. Probable original Cedar bearing tree in place, down, with no identifying
marks. Checks well with original, notes which note corner in south margin of swamp.

Corner placed and witnessed on 28 August 1958 with Norman J. Karsten.

SURVEYORS SEAL



SIGNED Henry S. Peterson
REGISTERED LAND SURVEYOR

DATE 9/15/58