

MICHIGAN  
DEPARTMENT OF CONSERVATION  
FORESTRY DIVISION

LAND CORNER RECORD

T. 40 NR. 28W

Dickinson COUNTY

DESCRIPTION OF CORNER 1/4 Cor. between Secs: 3-4

DESCRIPTION OF CORNER MONUMENT 1" Pipe with 4" Brass Cap

WITNESSES TO CORNER 6" Cedar (1/4s NBT) N21°E 53 Lks.

5" Tamarack (1/4s NBT) S44°E 13½ Lks.

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Replaced 1/4 Cor. at old Cedar stump. This stump scribed "1/4" about 1925. Has been used as cor. since then. Cor. lies about 1½ chs. west of a straight line between sec. cors. Notes indicate cor. lies in swamp. A straight line would place cor. on high ground. Cor. placed and wit. 3/19/59.

SURVEYORS SEAL

*Billy D. Buckler*  
SIGNED Billy D. Buckler DATE 8/21/59  
REGISTERED LAND SURVEYOR