

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 40. NR. 28W.

Dickinson COUNTY

DESCRIPTION OF CORNER Sec. Cor. 3-4-9-10

DESCRIPTION OF CORNER MONUMENT 1" Pipe with 4" Brass Cap

WITNESSES TO CORNER 36" W. Pine (MBT) S41⁰W 217¹/₂ Lks.

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Replaced cor. at iron pipe. This pipe has been in place since prior to 1925 according to William Johnson, County Road Commissioner, Iron Mt. Position fits swamp edges to east and west and stream crossing to south. Cor. lies 1¹/₂ chs. north of road. Cor. placed and wit. 3/11/59.

SURVEYORS SEAL

Billy D. Buckler
SIGNED _____ Billy D. Buckler _____ DATE 8/27/59
REGISTERED LAND SURVEYOR