

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 40 NR. 28W

Dickinson COUNTY

DESCRIPTION OF CORNER Sec. Cor. 16-17-20-21

DESCRIPTION OF CORNER MONUMENT 1" Pipe with 4" Brass Cap

WITNESSES TO CORNER 9" Cedar (S20 NBT) S16°W 26 Lks.

9" B. Cherry (S21 NBT) S62°E 14½ Lks.

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Re-established cor. from swamp edges to north, east and west and to stream south. Position fits with good cors. north and east. Found old pine stub blazed on north and south sides about 3½ chs. north of cor. No evidence of original cor. Cor. placed and wit. 4/30/59 with N. J. Karsten, Ass't D.F.

SURVEYORS SEAL

Billy D. Buckler
SIGNED Billy D. Buckler DATE 8/14/59
REGISTERED LAND SURVEYOR