

MICHIGAN  
DEPARTMENT OF CONSERVATION  
FORESTRY DIVISION

LAND CORNER RECORD

T 40 NR 28 W

Dickinson

----- COUNTY

DESCRIPTION OF CORNER Section corner common to sections 11,12,13 and 14  
-----

DESCRIPTION OF CORNER MONUMENT 4" brass cap and 1" iron pipe  
-----

WITNESSES TO CORNER Cedar 8" N 32 W 7 links, marked S 11 NBT  
-----

Cedar 16" S 87 W 96 links, marked S 14 NBT  
-----

Cedar 12" S 3 E 29 links, marked S 13 NBT  
-----  
-----

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR  
RESTORED.

Replaced corner from original tamarack bearing tree ( 10 S35E 18 ) in fair  
condition, BT shows plain in overgrowth, and original spruce bearing tree in  
poor condition ( 8 N 74 E 18 ). Stump in place with notch plain on BT face.

Corner placed with Clarence Ryberg on 21 June 1962.

SURVEYORS SEAL

*Henry S. Peterson*

SIGNED Henry S. Peterson  
REGISTERED LAND SURVEYOR

DATE 6-22-62