

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 40. NR 28. W. . .

----- Dickinson ----- COUNTY

DESCRIPTION OF CORNER Section Corner common to Sections 23, 24, 25, 26.

DESCRIPTION OF CORNER MONUMENT 1" pipe with 4" brass cap. -----

WITNESSES TO CORNER 12" White Pine S 20° W 64 links -----

16" Sugar Maple N 70° W 22 links -----

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR
RESTORED.

Corner has been perpetuated by an unknown surveyor.

Old rifle barrel in ground.

White Pine stp. in proper position.

Distance to swamp edge south and east checks.

Corner placed and witnessed August 1, 1955.

SURVEYORS SEAL

SIGNED Billy D. Buckler DATE 2/16/56
REGISTERED LAND SURVEYOR