

DEC 18 1995

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED
035 NOV 21 AM 11:26

For corners in
Dickinson
(County)

Located In:

Corner Code #

- | | | |
|--------------------------------------|---------------------------|-------------|
| 1. Public Land Survey | T <u>40N</u> R <u>29W</u> | <u>A-13</u> |
| | T _____ R _____ | <u>B-11</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

REGISTER OF DEEDS
DICKINSON COUNTY
MICHIGAN

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11	●											
12	31	32	33	34	35	36						
13	●											

I, Robert F. Perkins, in a field survey on Oct. 10, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- | | |
|---|---|
| A-13 Southwest Corner, Section 31
Post J. Mullett, D.S. 1848
Original Bearing Trees
Y.Pine 24" S36°E 21 Lks.
Y.Pine 24" N58°W 26 Lks. | B-11 North 1/4 Corner, Section 31
Post J. Mullett, D.S. 1848
Original Bearing Trees
Birch 8" S75°E 7 Lks.
Birch 10" N54°E 21 Lks. |
|---|---|

ACCEPTED BY THE DICKINSON COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON

11-30-95
R.F.P.

COUNTY REPRESENTATIVE

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- | | |
|---|--|
| A-13 No Evidence of Original Corner or Accessories Found.
City of Norway Land Record indicates Location of Corner at <u>L</u> Roads N-S and West.
Found Rail Spike in <u>E</u> N-S Road at Old Road West and Fence line East.
Corner Researched in 1994. | B-11 No Evidence of Original Corner or Accessories Found.
City of Norway Land Record indicates Concrete Monument buried 1' in <u>L</u> Road.
Found 1" Iron Pipe buried 40" in Road at above Location. Pipe may be in Concrete.
Corner Researched in 1994. |
|---|--|

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- | | |
|--|--|
| A-13 Replaced Rail Spike with 2 1/2" Stamped D.C. Remon. Monument in Monument Box.
New Witnesses
Cherry 9" S79°E (M.B.) 42.62'
Oak 24" S78°W (M.B.) 78.90'
Oak 3" N78°E (M.B.) 36.72'
P.Pole #71-2396 N11°W (M.B.) 89.50'
Carsonite Stake S79°E (M.B.) 33.0' | B-11 Set 2 1/2" Stamped D.C. Remon. Monument in Monument Box over above Found Iron Pipe.
New Witnesses
3" Stamped D.C. Remon. W.C. N10°E (M.B.) 31.80'
Maple 4" N48°E (M.B.) 60.77'
P.Pole #88-25659 S70°E (M.B.) 119.74'
P.Pole #71-2412 S89°W (M.B.) 159.25'
Placed Carsonite Marker at <u>Witness</u> Corner. |
|--|--|

Signed by Robert F. Perkins

Date Nov. 7, 1995

Surveyor's Michigan License No. 12027

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 23, 1991
NO. REV. 2002 MAY 1993
REVISED JAN. 1995

