

MAR 03 1998

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED
1997 DEC 10 PM 3:57

For corners in <u>Dickinson</u> (County)	Located In:	Corner Code #
Norway Twp.		
1. Public Land Survey	T 40N R 29W	<u>D-5</u>
	T ___ R ___	D-3
	T ___ R ___	
	T ___ R ___	
2. Property Controlling in Section	S ___ T ___ R ___	
	S ___ T ___ R ___	
3. Miscellaneous Property in Section	S ___ T ___ R ___	
	S ___ T ___ R ___	

REGISTER OF DEEDS
LICKINGWON COUNTY
RON MULLETT, CLERK

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3			●										
4	7		8		9		10		11		12		
5			●										
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Robert F. Perkins, in a field survey on Sept. 11, 1997, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

D-5 $\frac{8}{17}$ Corner
Post by James Mullett, D.S. 1849
Original Bearing Trees
Sugar 4" S13°W 10 Lks.
W.Pine 10" N10°W 15 Lks.

D-3 $\frac{5}{8}$ Corner
Post by James Mullett, D.S. 1849
Original Bearing Trees
Black Ash 10" N21°E 22 Lks.
Hemlock 8" S48°E 28 Lks.

ACCEPTED BY THE DICKINSON COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON 12-9-97
RFP

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner: COUNTY REPRESENTATIVE

D-5 No evidence of Original Corner or Accessories Found.
Found 1" Iron Pipe with 4" D.N.R. Brass Cap set by D.C. DeLaMater, RLS in 1955.
No Witnesses available in 1955.
(Old Report #46)

D-3 No evidence or Original Corner or Accessories Found.
Found 1" Iron Pipe with D.N.R. 4" Brass Cap set by D.C. DeLaMater, RLS in 1955.
1955 Bearing Trees:
Hemlock 16" S15°W 26 Lks.
Spruce 8" S63°E 71 Lks.
Rock Face North 61 Lks.
(Old Report #50)

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

D-5 Found and Accepted above described Monument.
New Witnesses:
Cedar 2" N86°E (M.B.) 9.86'
Cedar 4" S15°E (M.B.) 12.42'
Cedar 4" S67°W (M.B.) 8.28'
Fir 7" N18°E (M.B.) 15.45'
Carsonite Marker North 1.0'

D-3 Found and Accepted above described Monument.
New Witnesses:
Maple 8" N41°E (M.B.) 24.00'
Maple 8" S85°W (M.B.) 19.75'
* Hemlock 16" S15°W 17.60'
* Spruce 12" S63°E 46.78'
Carsonite Marker North 1.0'
Rock Face North 40.3'

* Existing 1955 B.T.

Signed by Robert F. Perkins

Date Nov. 19, 1997

Surveyor's Michigan License No. 12027

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, MAY 26, 1994, REVISED MAY 4, 1996, REVISED JAN 1997

