

MAR 03 1998

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED

1997 DEC 10 PM 3:57

| | | |
|--|---------------------------|---------------|
| For corners in <u>Dickinson</u> (County) | Located In: | Corner Code # |
| Norway Twp. | | |
| 1. Public Land Survey | T <u>40N</u> R <u>29W</u> | <u>E-1</u> |
| | T _____ R _____ | <u>E-2</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

REGISTER OF DEEDS
 DICKINSON COUNTY
 601 N. W. 10th St. (1990)

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

| | | | | | | | | | | | | |
|----|----|----|----|----|----|----|---|---|---|---|---|---|
| A | B | C | D | E | F | G | H | I | J | K | L | M |
| 2 | 6 | 5 | 4 | 3 | 2 | 1 | | | | | | |
| 3 | | | | | | | | | | | | |
| 4 | 7 | 8 | 9 | 10 | 11 | 12 | | | | | | |
| 5 | | | | | | | | | | | | |
| 6 | 18 | 17 | 16 | 15 | 14 | 13 | | | | | | |
| 7 | | | | | | | | | | | | |
| 8 | 19 | 20 | 21 | 22 | 23 | 24 | | | | | | |
| 9 | | | | | | | | | | | | |
| 10 | 30 | 29 | 28 | 27 | 26 | 25 | | | | | | |
| 11 | | | | | | | | | | | | |
| 12 | 31 | 32 | 33 | 34 | 35 | 36 | | | | | | |
| 13 | | | | | | | | | | | | |

I, Robert F. Perkins, in a field survey on Sept. 23, 19 97, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

E-1 Northeast Corner, Section 5
 Post by J.H. Mullett, D.S. 1848
 Original Bearing Trees
 Hemlock 24" S55°W 25 Lks.
 Hemlock 10" S57°E 40 Lks.

E-2 1/4 Corner to Sections 5/4
 Post by J.H. Mullett, D.S. 1849
 Original Bearing Trees
 W.Pine 14" N12°W 05 Lks.
 Cedar 8" N46°E 18 Lks.

ACCEPTED BY THE DICKINSON COUNTY
 SURVEY PEER GROUP AS THE OFFICIAL
 CORNER UNDER MICHIGAN PUBLIC ACT
 345 OF 1990 AT A MEETING HELD ON
12-9-97
R.F.P.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner: COUNTY REPRESENTATIVE

E-1 No Evidence of Original Corner or Accessories Found.
 Found 1" Iron Pipe with 4" D.N.R. Brass Cap set by D.C. DeLaMater, RLS in 1955.
 No Witnesses available at that time.
 (Old Report #61)

E-2 Found Remains of Original Pine B.T. Stump N12°W 3.3'.
 Found 1" Iron Pipe with 4" D.N.R. Brass Cap Set by D.C. DeLaMater, RLS in 1955.
 1955 Bearing Trees:
 W. Ash 9" N13°E 31 Lks.
 Y. Birch 24" N60°W 25 Lks.
 (Old Report #53)

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E-1 Found and Accepted above described Monument.
 New Witnesses:
 Maple 8" S21°W (M.B.) 24.49' Nail/Tag
 Maple 7" S66°E (M.B.) 16.09' Nail/Tag
 Maple 6" N28°E (M.B.) 34.98' Nail/Tag
 Maple 3" N79°W (M.B.) 17.70' Nail/Tag
 Carsonite Marker South 1.1'

E-2 Found and Accepted above Described Monument.
 New Witnesses:
 Maple 3" N46°E (M.B.) 8.12' Nail/Tag
 Maple 3" S25°E (M.B.) 46.86' Nail/Tag
 Maple 8" N83°W (M.B.) 22.13' Nail/Tag
 Ironwood 3" S12°W (M.B.) 17.43' Nail/Tag
 Carsonite Marker North 1.0'

Signed by Robert F. Perkins
 Surveyor's Michigan License No. 12027

Date Nov. 19, 1997

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN 28, 1997

