

MAY 07 1997

COMMISSION

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

**RECORDED**  
 1996 DEC 18 AM 11:16

For corners in

|                                    |                           |               |
|------------------------------------|---------------------------|---------------|
| <u>Dickinson</u><br>(County)       | Located In:               | Corner Code # |
| 1. Public Land Survey              | T <u>40N</u> R <u>29W</u> | <u>E-7</u>    |
|                                    | T _____ R _____           | _____         |
|                                    | T _____ R _____           | _____         |
|                                    | T _____ R _____           | _____         |
| 2. Property Controlling in Section | S _____ T _____ R _____   | _____         |
|                                    | S _____ T _____ R _____   | _____         |
| 3. Miscellaneous Property in Sec.  | S _____ T _____ R _____   | _____         |
|                                    | S _____ T _____ R _____   | _____         |

REGISTER OF DEEDS  
 DICKINSON COUNTY  
 IRON MOUNTAIN, MI 49801

①

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

I, Michael Mileski, in a field survey on 29 October, 19 96 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

| A  | B  | C | D  | E | F  | G | H  | I | J  | K | L  | M |
|----|----|---|----|---|----|---|----|---|----|---|----|---|
|    | 6  | 5 |    | 4 |    | 3 |    | 2 |    | 1 |    |   |
| 3  |    |   |    |   |    |   |    |   |    |   |    |   |
| 4  | 7  |   | 8  |   | 9  |   | 10 |   | 11 |   | 12 |   |
| 5  |    |   |    |   |    |   |    |   |    |   |    |   |
| 6  | 18 |   | 17 |   | 16 |   | 15 |   | 14 |   | 13 |   |
| 7  |    |   |    |   |    |   |    |   |    |   |    |   |
| 8  | 19 |   | 20 |   | 21 |   | 22 |   | 23 |   | 24 |   |
| 9  |    |   |    |   |    |   |    |   |    |   |    |   |
| 10 | 30 |   | 29 |   | 28 |   | 27 |   | 26 |   | 25 |   |
| 11 |    |   |    |   |    |   |    |   |    |   |    |   |
| 12 | 31 |   | 32 |   | 33 |   | 34 |   | 35 |   | 36 |   |
| 13 |    |   |    |   |    |   |    |   |    |   |    |   |

A. Description of original monument and accessories and/or subsequent restoration:

E-7; Section Corner common to Sections 16, 17, 20, and 21, T40N, R29W;

See back of form.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

E-7; Section Corner common to Sections 16, 17, 20, and 21, T40N, R29W;

ACCEPTED BY THE DICKINSON COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON 12-17-96  
R.O.P.  
 COUNTY REPRESENTATIVE

Found a 1" x 42" galvanized iron pipe with a 4" brass cap as set by Mr. DeLaMater in 1954 alongside a 2" x 36" iron pipe. Mr. DeLaMater's monument was found to be in agreement with his new bearing trees as described in Part A. Replaced Mr. DeLaMater's monument with a standard county monument described in Part C. Accepted as a careful and faithful perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E-7; Section Corner common to Sections 16, 17, 20, and 21, T40N, R29W;

Set a 5/8" x 36" aluminum rod with a 3" aluminum cap stamped as to location projecting 4" above the ground.

|              |         |               |       |        |
|--------------|---------|---------------|-------|--------|
| Set 7" spike | NW/side | 7" Cedar      | N53°E | 22.43' |
| Set 7" spike | NW/side | 9" Cedar      | S22°W | 11.64' |
| Set 7" spike | SW/side | 9" Cedar      | N65°W | 12.46' |
| Set 7" spike | E/side  | 8" Cedar      | N15°W | 49.35' |
|              |         | Location Post | North | 3.0'   |



All of the above new bearing trees are marked with upper and lower blazes. The lower blaze is scribed "NBT". Both blazes as well as a band around the tree at the upper blaze are painted red.

Signed by Michael Mileski  
 Surveyor's Michigan License No. 39091

Date 3 DEC 1996  
 Bk. 17M pp 12 & 13