

MAY 07 1997

COMMISSION LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED
1996 DEC 18 AM 11:16

For corners in

Dickinson Located In: Corner Code #
(County)

1. Public Land Survey T 40N R 29W G-7
T _____ R _____
T _____ R _____
T _____ R _____

2. Property Controlling S _____ T _____ R _____
in Section S _____ T _____ R _____

3. Miscellaneous S _____ T _____ R _____
Property in Sec. S _____ T _____ R _____

REGISTER OF DEEDS
DICKINSON COUNTY
IRON MOUNTAIN, MI 49801

3

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Michael Mileski, in a field survey on 12 November, 19 96 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G-7; Section Corner common to Sections 15, 16, 21, and 22, T40N, R29W;

See back of form.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner: 12-17-96

RSP
COUNTY REPRESENTATIVE

G-7; Section Corner common to Sections 15, 16, 21, and 22, T40N, R29W;

Found a 1" x 42" galvanized iron pipe with a 4" brass cap as set by Mr. Buckler in 1955. Mr. Buckler's monument was found to be in agreement with his new bearing trees as described in Part A. Replaced Mr. Buckler's monument with a standard county monument described in Part C. Accepted as a careful and faithful reestablishment of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-7; Section Corner common to Sections 15, 16, 21, and 22, T40N, R29W;

Set a 5/8" x 36" aluminum rod with a 3" aluminum cap stamped as to location projecting 4" above the ground.

Set 7" spike	SW/side	6" Sugar Maple	S69°E	29.16'
Set 7" spike	E/side	10" White Spruce	S18°E	32.34'
Set 7" spike	NW/side	14" White Spruce	S16°W	24.45'
Set 7" spike	SE/side	5" White Spruce	S48°W	7.39'
Set 7" spike	SW/side	6" Red Maple	N32°W	44.25'
		Location Post	North	3.0'

All of the above new bearing trees are marked with upper and lower blazes.

The lower blaze is scribed "NBT". Both blazes as well as a band around the tree at the upper blaze are painted red.



Signed by Michael Mileski

Date 3 DEC 1996

Surveyor's Michigan License No. 39091

Bk. 17M pp 20 & 21