

JAN 04 2001

SECTION

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED

1997 DEC 10 PM 3:57

For corners in Dickinson (County) Located In: Norway Twp. Corner Code #

1. Public Land Survey	T <u>40N</u> R <u>29W</u>	<u>I-1</u>
	T _____ R _____	<u>K-1</u>
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

REGISTER OF DEEDS
DICKINSON COUNTY
MICHIGAN

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L
2	6	5	4	3	2	1					
3											
4	7	8	9	10	11	12					
5											
6	18	17	16	15	14	13					
7											
8	19	20	21	22	23	24					
9											
10	30	29	28	27	26	25					
11											
12	31	32	33	34	35	36					
13											

I, Robert F. Perkins, in a field survey on Sept. 23, 1997, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

I-1	Northeast Corner, Section 3 Post by J.H. Mullett, D.S. 1848 Original Bearing Trees Hemlock 6" S23°E 15 Lks. Hemlock 6" S19°W 07 Lks.	K-1	Northeast Corner, Section 2 Post by J.H. Mullett, D.S. 1848 Original Bearing Trees Sugar 16" S28°E 25 Lks. Birch 8" S25°W 39 Lks.
-----	--------------------------------------------------------------------------------------------------------------------------------------------------	-----	-----------------------------------------------------------------------------------------------------------------------------------------------

ACCEPTED BY THE DICKINSON COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 346 OF 1990 AT A MEETING HELD ON

12-9-97

ROP

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner: COUNTY REPRESENTATIVE

I-1	No Evidence of Original Corner or Accessories Found. Found 1" Iron Pipe with 4" D.N.R. Brass Cap Set by B.D. Buckler, RLS in 1956. 1956 Bearing Trees: Balsam 12" S72°W 40 Lks. W. Birch 9" S31°E 65 Lks. (Old Report #65)	K-1	No Evidence of Original Corner or Accessories Found. Found 1" Iron Pipe with 4" D.N.R. Brass Cap Set by D.C. DeLaMater, RLS in 1955. 1955 Bearing Trees: Hemlock 16" S46°E 105 Lks. Hemlock 18" S16°W 148 Lks. (Old Report #67)
-----	-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------	-----	------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I-1	Found and Accepted above Described Pipe Monument. New Witnesses: Maple 5" N14°W (M.B.) 19.30' Nail/Tag Maple 7" N67°E (M.B.) 31.80' Nail/Tag Maple 6" S22°E (M.B.) 25.59' Nail/Tag Maple 3" S85°W (M.B.) 12.48' Nail/Tag Carsonite Stake North 1.0'	K-1	Found and Accepted above Described Pipe Monument. New Witnesses: Y. Birch 10" N05°E (M.B.) 18.75' Nail/Tag Maple 7" S19°W (M.B.) 18.92' Nail/Tag Maple 3" N83°W (M.B.) 28.48' Nail/Tag * Hemlock 18" S46°E (M.B.) 69.9' Nail/Tag Carsonite Marker North 0.8' * Existing 1955 B.T.
-----	-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------	-----	------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------

Signed by Robert F. Perkins

Date Nov. 19, 1997

Surveyor's Michigan License No. 12027

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS JAN. 24, 1991

LIBER 002 PAGE 320

