

MAY 07 1997

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED
1996 DEC 18 AM 11:15

For corners in

Dickinson

(County)

Located in:

Corner Code #

- 1. Public Land Survey T 40N R 29W I-12
2. Property Controlling in Section S T R
3. Miscellaneous Property in Sec. S T R

REGISTER OF DEEDS
DICKINSON COUNTY
IRON MOUNTAIN, MI 49801

6

Register of Deeds Stamp & File Number

- 4. Lot No.
5. Private Claims

I, Michael Mileski, in a field survey on 1 November, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

I-12; One-quarter Corner common to Sections 34 and 35, T40N, R29W;

See back of form.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I-12; One-quarter Corner common to Sections 34 and 35, T40N, R29W;

Found a 2" x 54" iron pipe projecting 26" above the ground in agreement with Mr. Buckler's new bearing trees as described in Part A. Replaced this monument with a standard county monument described in Part C. Accepted as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I-12; One-quarter Corner common to Sections 34 and 35, T40N, R29W;

Set a 5/8" x 36" aluminum rod with a 3" aluminum cap stamped as to location projecting 4" above the ground.

- i) Set 7" spike E/side 12" Cedar N29°E 31.35'
ii) Set 7" spike N/side 11" White Pine S70°E 19.48'
iii) Set 7" spike SE/side 12" Cedar S30°W 12.65'
iv) Set 7" spike S/side 9" Cedar N81°W 19.98'
v) Set 7" spike N/side 12" Cedar N56°W 21.53'
vi) Location Post North 3.0'

(i), (ii), and (iv) are marked with upper and lower blazes. The lower blaze is scribed "NBT". Both blazes as well as a band around the tree at the upper blaze are painted red.

(iii) and (v) are Buckler new bearing trees and are further described in Part A.

Grid table with columns A-M and rows 1-13. A dot is marked at row 12, column J.

ACCEPTED BY THE DICKINSON COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON

12-17-96
RDP
COUNTY REPRESENTATIVE



Signed by [Signature]

Date 3 DEC 1996

Surveyor's Michigan License No. 39091

Bk. 17M pp 22 & 23