

SURVEY & REMONUMENTATION

MAR 03 1998

SECTION

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED

1997 DEC 10 PM 3:57

For corners in

Dickinson
(County)

Located In:

Corner Code #

Norway Twp.

1. Public Land Survey	T	<u>40N</u>	R	<u>29W</u>	<u>M-13</u>
	T	---	R	---	<u>J-11</u>
	T	---	R	---	---
	T	---	R	---	---
2. Property Controlling In Section	S	---	T	---	---
	S	---	T	---	---
3. Miscellaneous Property in Section	S	---	T	---	---
	S	---	T	---	---

REGISTER OF DEEDS
DICKINSON COUNTY
RON MULLETT, CLERK

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Robert F. Perkins a field surveyor on Sept. 5, 1997 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

M-13 Southeast Corner, Section 36
Post by H. Brevort 1847
Original Bearing Trees
Sugar 12" N29°W 24 Lks.
Hemlock 14" N66°E 33 Lks.

J-11 $\frac{1}{4}$ Corner $\frac{26}{35}$
Post by James Mullett, D.S. 1849
Original Bearing Trees
Birch 10" S66°E 19 Lks.
Maple 10" S44°W 25 Lks.

APPROVED BY THE DICKINSON COUNTY
CLERK AS THE OFFICIAL
GROUP UNDER MICHIGAN PUBLIC ACT
1990 AT A MEETING HELD ON
12-9-97
RAM

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

M-13 Found 1" Iron Pipe with 4" Brass Cap D.N.R. Marker set by Billy Buckler, R.L.S. in 1961 (Old Report #620).
1961 Bearing Trees
Elm 7" S04°E 167 Lks.
Maple 14" N80°W 81 $\frac{1}{2}$ Lks.

J-11 W.E. Johnson, C.E. tied into 2" Iron Pipe at Cedar Post in 1934 and made B.T.'s:
Cedar 6" N21°E 7.5'
Hemlock 4" N31°E 12.4'
Balsam 3" N78°E 11.9'
9-5-97: Found above 2" Iron Pipe and Point of Cedar Post in muck. Found Stump of B.T. Cedar 6" Corner research in 1996.


C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-13 Found above described Monument in place. New Witnesses
Spruce 18" N12°E (M.B.) 9.65' Nail/Tag
R. Pine 9" S06°E (M.B.) 86.43' Nail/Tag
Tamarack 8" S49°W (M.B.) 54.26' Nail/Tag
Carsonite Marker South 1.6'
Existing 1961 B.T.: Db. Sugar Maple 30" N78°W (M.B.) 53.60'

J-11 Accepted above Pipe/Post as Best Available Evidence of Corner Location. Set 2 $\frac{1}{2}$ Stamped Re-Mon. Corner at Old Post Point.
New Witnesses:
S. Maple 6" S70°W (M.B.) 25.70' Nail/Tag
Cedar 8" N14°E (M.B.) 25.63' Nail/Tag
Cedar 9" N68°E (M.B.) 31.58' Nail/Tag
Lynn 8" S07°E (M.B.) 34.60' Nail/Tag
Carsonite Marker South 1.5'

Signed by Robert F. Perkins

Surveyor's Michigan License No. 12027



Date Nov. 19, 1997

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 23, 1971
REVISED MAY 14, 1975
REVISED JAN., 1983