

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED

1998 DEC 14 PM 12:25

For corners in

Dickinson Located in: _____ Corner Code # _____
 (County)
Norway Twp.
 1. Public Land Survey T 40NR 29W K-2
 T _____ R _____ K-8
 T _____ R _____
 T _____ R _____
 2. Property Controlling S _____ T _____
 in Section S _____ T _____
 3. Miscellaneous S _____ T _____
 Property in Sec. S _____ T _____

REGISTER OF DEEDS
 DICKINSON COUNTY
 200 MAIN ST. S.W. GRAND RAPIDS, MI 49503

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____ SECTION _____
 5. Private Claims _____

I, Robert F. Perkins, in a field survey on Sept. 24, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2	●	1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23	●	24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

K-2 ¼ Corner Common to Sections 1 & 2
 Post by J.H. Mullett, D.S. 1849
 Original Bearing Trees
 Fir 12" S73°W 10 Lk.
 Hemlock 12" N47°E 30 Lk.

K-8 ¼ Corner Common to Sections 23 & 24
 Post by J.H. Mullett, D.S. 1849
 Original Bearing Trees
 Sugar 10" N74°W 15 Lk.
 Cedar 12" N70°E 10 Lk.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

K-2 No Evidence of Original Corner or Accessories Found.
 Found 1½" Iron Pipe Set in 1935 by W.C. Johnson, C.E.
 Dickinson County Road Commission File A-8
 Corner Researched 11-19-97

K-8 No Evidence of Original Corner or Accessories Found.
 Found 1½" Iron Pipe Set by W.C. Johnson, C.E. in 1935.
 Dickinson County Road Commission File A-8, #46, Sh.#3
 Corner Researched 11-19-97

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-2 Accepted Iron Pipe described in "B" above. Placed 2½" Stamped D.C. Remon. Corner inside of Existing Iron Pipe.
 New Witnesses
 Maple 4" S22°E(M.B.) 25.08' Nail/Tag
 Maple 13" N75°E(M.B.) 24.24' Nail/Tag
 Maple 4" N09°E(M.B.) 15.42' Nail/Tag
 Maple 10" S60°W(M.B.) 5.10' Nail/Tag
 Placed Carsonite Marker 1.0' North.

K-8 Accepted Iron Pipe described in "B" above. Replaced same with 2½" Stamped D.C. Remon. Corner.
 New Witnesses:
 Maple 6" N13°W(M.B.) 20.56' Nail/Tag
 Maple 3" S25°W(M.B.) 13.68' Nail/Tag
 Maple 3" S32°E(M.B.) 17.35' Nail/Tag
 Ironwood 3" N86°E(M.B.) 30.88' Nail/Tag
 Placed Carsonite Marker 1.0' East.

Signed by Robert F. Perkins Date Oct. 28, 1998
 Surveyor's Michigan License No. 12027

ACCEPTED BY THE DICKINSON COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 848 OF 1990 AT A MEETING HELD ON 12-7-98

